

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22311-00-00  
Spot: SENW Sec/Twnshp/Rge: 5-11S-18W  
3300 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: SALINE VALLEY GRAZING Well #: 2  
County: ELLIS Total Vertical Depth: 3575 feet

Operator License No.: 32250  
Op Name: KENNY BROWN ENTERPRISES LLC  
Address: BOX 277  
HAYS, KS 67601

PROD Size: 4.5 feet: 3573 w/175 sxs cmt  
SURF Size: 8.625 feet: 170 w/130 sxs cmt

*\$116<sup>19</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/16/2005 8:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Revd. from: STEVE RUDER Company: KENNY BROWN ENTERPRISES LL Phone: (785) 628-3384

Proposed Plugging Method: Ordered out 180 sxs Swift Multi-Density cement and 600# hulls.  
08-06-1982 - Squeezed 850' w/200 sxs.  
08-22-2000 - Squeezed 2626' - 2637' w/250 sxs.  
T.O.P. Fish 2476'. Unable to washover - decided to P&A.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/16/2005 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:  
Ran tubing to 2170'. Swift Services pumped 75 sxs Swift Multi-Density cement with 200# hulls.  
Pulled tubing to 1400'. Swift Services pumped 30 sxs SMD with 200# hulls - circulated cement.  
PTOH. Squeezed 40 sxs SMD with 200# hulls.  
Max. P.S.I. 200#. S.I.P. 0#. Cement 250' down.  
Hooked up to backside. Swift Services pumped 35 sxs SMD.  
Max. P.S.I. 400#. S.I.P. 200#.  
Will check casing and top off.  
05-19-2005 - Cement 350'. Swift Services topped of with 20 sxs SMD.  
Hole full.

Perfs:

RECEIVED  
JUN - 1 2005  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

INVOICED

DATE 6-1-05  
INV. NO. 2005061647

MAY 23 2005

KENNY BROWN ENTERPRISES #2 SALINE VALLEY 5-11-18W  
 DRAWER 340 PLAINVILLE, KS 67663 GRAZING C SE NW

CONTR DREILING OIL, INC. CTY ELLIS

GEOL LARRY GRAY FIELD RICHARDS

E 2075 KB CM 3/2/81 CARD ISSUED 6/18/81 IP P 35 BO & 50 BWPD  
 2070 GL KC 3442-3530 OA

API 15-051-22,311

	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
AMH	1396	+ 679	
TOP	3051	- 976	
HEEB	3272	-1197	
TOR	3287	-1212	
LKC	3312	-1237	
BKC	3549	-1474	
RTP	3575	-1500	
NO LOG			

8-5/8" 170/130sx, 4 1/2" 3573/175sx

NO DSTS  
 MICT - CO, PF( KC) 3442-3530 OA,  
 SWB GSO, POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

INDEXED