

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07094-00-00
Spot: SENWSE Sec/Twnshp/Rge: 23-19S-12W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BRODIE Well #: 7
County: BARTON Total Vertical Depth: 3393 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N.
VALLEY CENTER, KS 67147

PROD Size: 5.5 feet: 3381 150 SX
SURF Size: 8.625 feet: 238 115 SX

#110²⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/17/2005 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: DONALD W. SANDERS Company: DAYSTAR PETROLEUM, INC. Phone: (620) 669-7391

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/17/2005 12:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 640' and 1425'.
Ran tubing to 2021'.
Pumped 90 sxs 60/40 pozmix - 10% gel cement with 300# hulls.
Pulled to 1000' - pumped 185 sxs cement with 300# hulls.
Pulled to 500' - circulated with 50 sxs cement.
Tied onto casing and pumped 25 sxs cement.
Cement circulated up annulus.
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3375	3387		
3143	3147		
3099	3107		
2988	2996		

RECEIVED
JUN - 1 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

10.

Signed Case Morris
(TECHNICIAN)

INVOICED
DATE 6-1-05
INV. NO. 2005061649

MAY 25 2005

ALACDIN & HANNUM

#7

BRODIE

53 23-19-12W
SE NW SE

Contr. HANNUM DRILLING CO.

BARTON

County

E. 1809

Comm.

Comp. 1-20-50

IP 204 BOPD

PHY POT

Tops	Depth	Datum
Arh	620	+1179
TOP	2726	-917
HEEB	2970	-1167
BR LM	3084	-1275
LANS	3108	-1299
CONG	3373	-1564
A+B	3378	-1569
T.O.	3392	-1583

Casing

8" 238 SWB 20 80/10 HRS
 5" 3381 ACID 100J
 SWB 4 1/2 BOPH

HAMMER NORTH POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

PROLOG