

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 163 - 21,019-00-00 (of this well)
Lease Owner Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas 67202
Lease (Farm Name) REED Well No. 1
Well Location SE NW NW Sec. 14 Twp. 7S Rge. 19W (E) (W) X
County Rooks Total Depth 3470' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 1:30 a.m., 02-21-80

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Leon Strecker Address 223 10th Street, Wakeeney, Kansas

Plugging Contractor Abercrombie Drilling, Inc. License No. _____

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to: MAR 3, 1980

Name Abercrombie Drilling, Inc.

Address 801 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent
Jack L. Partridge
Date: February 28, 1980

KANSAS DRILLERS LOG

IMPORTANT
 Kans. Geo. Survey request
 samples on this well.

S. 14 T. 7 R. 19 ^W/_W
 Loc. SE NW NW
 County ROOKS

API No. 15 — 163 — 21,019-00-00
County Number

Operator Ambercrombie Drilling Co,

Address 801 Union Center, Wichita, Ks 67202


Well No. 1 Lease Name Reed

Footage Location
990' feet from XX (S) line 990' feet from (E) XX line

Principal Contractor Abercrombie Drilling Inc. Geologist Bill Darrow

Spud Date February 12, 1980 Total Depth 3470' P.B.T.D. 3500'

Date Completed February 21, 1980 Oil Purchaser _____



Locate well correctly
 Elev.: Gr. 1945'
 DF 1948' KB 1950'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 3/4"	8-5/8"	20#	248'	common	175	3% Ca.Cl. 2% gel.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

MAR 3 1980

INITIAL PRODUCTION

Date of first production _____		Producing method (flowing, pumping, gas lift, etc.) _____			
RATE OF PRODUCTION PER 24 HOURS	Oil _____ bbls.	Gas _____ MCF	Water _____ bbls.	Gas-oil ratio _____	CFPB _____
Disposition of gas (vented, used on lease or sold) _____			Producing interval (s) _____		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **Abercrombie Drilling, Inc.** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: **Dry Hole**

Well No. **1** Lease Name **Reed**

S **14** T **7S** R **19W** E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand and shale	0	978	SAMPLE TOPS:	
Sand	978	1184		
Shale	1184	1295	Anhydrite	1475' (+ 475)
Sand and shale	1295	1475	B/Anhydrite	1500' (+ 450)
Shale and Anhydrite	1475	1500	Heebner	3115' (-1165)
Shale	1500	1615	Toronto	3140' (-1190)
Sand and shale	1615	1880	Lansing	3157' (-1207)
Shale	1880	2346	B/KC	3378' (-1428)
Lime and shale	2346	2774	Cong.	3393' (-1433)
Shale and lime	2774	2955	Arbuckle	3424' (-1474)
Lime	2955	3470		
Rotary Total Depth		3470		
DST #1 (3180-3210') 30", 45", 30", 30" Rec. 20' thin mud. IFP 45-45, IBHP 789, FFP 45-54, FBHP 491.			ELECTRIC LOG TOPS:	
DST #2 (3227-3265') 30", 45", 60", 45" Rec. 130' mdy wtr with few oil spots. IFP 43-65, IBHP 980, FFP 76-109, FBHP 104			Heebner	3113' (-1163)
DST #3 (3303-3318') 30", 45", 60", 45" Rec. 220' gip, 90' mco (70% oil) IFP 21-32, IBHP 863, FFP 43-54, FBHP 831.			Toronto	3135' (-1185)
DST #4 (3321-3346') 30", 30", 30", 30" Rec. 10' mud. IFP 21-21, IBHP 32, FFP 21-21, FBHP 32.			Lansing	3153' (-1203)
DST #5 (3343-3370') 30", 45", 30", 30" Rec. 90' thin mud with oil spots. IFP 76-76, IBHP 831, FFP 87-87, FBHP 565.			B/KC	3373' (-1423)
			Cong.	3394' (-1444)
			Arbuckle	3424' (-1474)
			LTD	3471'
			RTD	3470'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

Jack L. Partridge
Signature

Jack L. Partridge, Asst. Sec.-Treas.
Title

February 28, 1980
Date



JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAY

Governor
Chairman
Commissioner
Commissioner

Carol J. Larson, Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

WELL PLUGGING AUTHORITY

Well No.	#1
Lease	Reed
Description	SE NW NW
Section	14-7S-19W
County	Rooks
Total Depth	3470'

Abercrombie Drilling Inc., Plugging Contractor
801 Union Center,
Wichita, Kansas.
67202


Abercrombie Drilling Inc.,

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) day from the above date.

Yours very truly,


J. LEWIS BROCK, Administrator

Marion Schmidt, 2104 Canterbury Rd., Hays, Kansas. 67601
is hereby assigned to supervise the plugging of the above named well