

15-163-01317-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

Rev. 12-4-81
FORM CP-1

RECEIVED
STATE CORPORATION COMMISSION
OCT 25 1982
OCT 25 1982
CONSERVATION DIVISION
Wichita Kansas

WELL PLUGGING APPLICATION FORM
File One Copy

API NUMBER 514 (of this well)
(This must be listed; if no API# is available, please note drilling completion date.)

LEASE OWNER Southern States Oil Company (#5354)

ADDRESS P.O. Box 1365 @ Great Bend, Ks. 67530 PHONE # (316) - 792-2585

LEASE (FARM NAME) Bessie Burton WELL NO. 1

WELL LOCATION NW SW SW SEC. 14 TWP. 7 S RGE. 19 W (~~East~~)(West) X

COUNTY Rooks TOTAL DEPTH 3416' FIELD NAME _____

OIL WELL GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

WELL LOG ATTACHED WITH THIS APPLICATION AS REQUIRED? Yes ACO-1 filed? _____
(If not, state reason why)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN immediately

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Buster Humphrey ADDRESS Hays, Kansas

PHONE # (913) - 625-2028

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050

ADDRESS Box 347 @ Chase, Kansas, 67524 PHONE # (316) - 938-2457

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO:

NAME Southern States Oil Company

ADDRESS P.O. Box 1365 @ Great Bend, Ks. 67530 PHONE # (316) - 792-2585

AND PAYMENT WILL BE GUARANTEED BY APPLICANT /OR ACTING AGENT.

SIGNED: *R. [Signature]*
Applicant /or Acting Agent

DATE: 10-20-82

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK
WICHITA 5, KANSAS

15-163-01317-00-00


COMPANY Magnolia Petroleum Company

SEC. 14 T. 7S R. 19W
LOC. NW SW SW

FARM Bessie Burton NO. 1

TOTAL DEPTH 3416 K B. PB 3390
COMM. 9/12/51 COMP. 10/10/51
SHOT OR TREATED Acidized
CONTRACTOR Barnett Drilling, Inc.
ISSUED

COUNTY Rooks



CASING

20 10 3/4" set @ 184' & cem. w/150 sacks
15 1/2 8 1/4
12 1/2 6 1/2" set @ 3398 1/2' & cem. w/200 sacks
13 5 1/4

ELEVATION 1946 D.F.

PRODUCTION P 129 BO & 31 BW,
24 hours

FIGURES INDICATE BOTTOM OF FORMATIONS

shale	184
shale & shells	925
sand	1159
shale & shells	1430
anhydrite	1680
shale & shells	2205
shale & lime	2295
lime & shale	2357
shale & shells	2610
shale & lime	3020
lime	3416

Total Depth	3416 K.B.
Plug Back Depth	3390 "
Top Heebner	3090 "
Toronto	3113 "
Lansing	3129 "
Arbuckle	3397 "

DST 3096-3149, open 1 hour, rec. 280' heavily oil cut mud, BHP 1181#.
DST 3156-3204, open 1 hour, rec. 35' heavily oil cut mud, BHP 85#
DST 3272-91, open 1 hour, rec. 10' slightly oil cut mud, BHP 45#

Rotary total depth 3400.

DD to 3406, bailed 3 qts. oil per hour, no water, 3 hours.

Acidized w/500 gallons, swab. 3 qts. oil, 1 BW PH, 6 hours

DD to 3416, acidized w/500 gallons, bailed 4 GO & 2 BWPH 2 hours.

Set plug 3390, perf. 3320-36 w/47 sh, 3343-50 w/20 sh.

Acidized w/2000 gallons, swb. 5 BOPH, no water, 3 hours.

Set plug 3318, perf. 3303 1/2-12 w/24 sh., bailed 1 hour, all water.

Swabbed perfs. 3303 1/2-12, 2 BO & 2 BWPH, 3 hours.

Set plug 3295, perf. 3282-92 w/30 sh., tested 1 1/2 BO & 1/2 BWPH, 5 hours.

Set plug 3315. Acidized perfs. 3282-92 and 3303-12 w/2000 gallons, Swb 4 BO & 1 BWPH, 8 h

Drove plug to 3390

RECEIVED
STATE GEOLOGICAL COMMISSION
OCT 25 1982
OCT 25 1982
CONSERVATION DIVISION
Wichita Kansas

State of Kansas



15-163-01317-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202

October 29, 1982

THIS PERMIT

JAN 29 1983

EXPIRES

WELL PLUGGING AUTHORITY

Bessie Burton #1
NW SW SW
Sec. 14-7S-19W
Rooks
T.D. 3416'
Kelso Casing


Southern States Oil Company
P. O. Box 1365
Great Bend, KS 67530

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) days from the above date.

Yours very truly,



DELBERT J. COSTA, Administrator

Dist. #6 1014 Cody, Hays, KS 67601 (913) 628-1200

is hereby assigned to supervise the plugging of the above named well.

NOTE: If you are unable to contact District Plugging Agent at his regular number, call TOLL FREE 1-800-362-1358.