

15-163-20597-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1977
CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - - (of this well)
Lease Owner F & M Oil Company
Address 505 Union Center, Wichita, Kansas 67202
Lease (Farm Name) RISELEY Well No. 1
Well Location SW/NW/SW Sec. 2 Twp. 7 Rge. 19 (E) (W) X
County Rooks Total Depth 3532' Field Name
Oil Well X Gas Well Input Well SWD Well Rotary D & A
Well Log attached with this application as required yes
Date and hour plugging is desired to begin as soon as possible

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:
Gene Falkowski Address 505 Union Center, Wichita, KS 67202
Plugging Contractor Rockhold Engineering, Inc. License No. 670
Address Box 698, Great Bend, Kansas 67530

Invoice covering assessment for plugging this well should be sent to:
Name F & M Oil Company
Address 505 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: James W. Rockhold
Applicant or Acting Agent
James W. Rockhold
Date: June 14, 1977

JUN 14 1977

15-163-20597-00-00

CONTRACTOR'S WELL LOG

OPERATOR:
CONTRACTOR:
WELL NAME
LOCATION:

SPUD DATE:
COMPLETION DATE:

COPY

F & M Oil Company
Abercrombie Drilling, Inc.
RISELEY #1
SW NW SW Section 2-7S-19W
Rooks County, Kansas
February 19, 1976
March 1, 1976

0	60	Clay & Sand
60	72	Rock
72	180	Sand
180	540	Shale
540	1045	Shale & Sand
1045	1255	Sand
1255	1546	Shale
1546	1581	Anhydrite
1581	1960	Shale
1960	3248	Lime & Shale
3248	3532	Lime
	3532	Rotary Total Depth

Drilled 210' of 12½" hole. Ran 5 jts. of butted 8 5/8" surface Set @ 210' K.B. with 160 sx. Quick-Set cement. Cement circulated. Plug was down @ 8:00 p.m. February 19, 1976.

Ran 86 jts. 4½". Set @ 3331' K.B. Cem. with 150 sx. Common, 18% salt. Plug was down @ 7:00 p.m. March 1, 1976.

Sample Tops:

Anhydrite	1546 (+480)
B/Anhydrite	1581 (+445)

JUN 15 1977

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the RISELEY #1, SW NW SW Section 2-7S-19W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
Jerry A. Langrehr, Exec. V.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 3rd day of March, 1976.

Diane Steincamp
Diane Steincamp, Notary Public

My Commission Expires: February 18, 1980



State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

June 15, 1977

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Riseley
Description	SW NW SW Sec. 2-7-19W
County	Rooks
Total Depth	3532
Plugging Contractor	Rockhold Engineering, Inc.


**F & M Oil Company
505 Union Center
Wichita, Kansas 67202**

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Leo Massey, 109 West 15th, Hays, Kansas 67601
is hereby assigned to supervise the plugging of the above named well.