

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-159-04298-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 6/19/54

Well Operator: PROSPECT OIL & GAS CORP KCC License #: 6627
(Owner / Company Name) (Operator's)

Address: P O BOX 837 City: RUSSELL

State: KS Zip Code: 67665-0837 Contact Phone: (785) 483 - 6266

Lease: FREEMAN Well #: 5 Sec. 4 Twp. 21 S. R. 6 East West

C SE SE SW Spot Location / QQQQ County: RICE

660 330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

3300 2310 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 160 Cemented with: 150 Sacks

Production Casing Size: 5 1/2 Set at: 3467 Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3433-38 3380

Elevation: 1641 (G.L. / K.B.) T.D.: 3467 PBTD: 3446 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): AS KCC REQUIRES

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? NOT AVAILABLE TO US

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: BRAD HUTCHISON

Phone: (785) 483 - 6266 RECEIVED

Address: P O BOX 837 City / State: RUSSELL KS 67665 APR 18 2005

Plugging Contractor: QUALITY WELL SERVICE KCC License #: 31925 KCC WICHITA 05

Address: 401 W MAIN LYONS KS 67554 Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): ASAP 11-30-2004 Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11/20/04 Authorized Operator / Agent: [Signature] (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Quality Well Service, Inc.

401 West Main
Lyons, KS 67554

Invoice

Date	Invoice #
12/6/2004	616

Bill To
Prospect Oil & Gas Corp. PO Box 837 Russell, KS 67665-0837

P.O. No.	Terms	Lease Name
		Freeman #5

Description	Qty	Rate	Amount
Rig Time	28	135.00	3,780.00T
Trucking Floor	1	90.00	90.00T
Cement	5	9.00	45.00T
Ripping Pipe	2	140.00	280.00T
Water Truck	4	60.00	240.00T
Backhoe	2	62.00	124.00T
Phone Calls	1	10.00	10.00T
Clerical	1	10.00	10.00T
Wiping Rubber	1	15.00	15.00T
11-24-04 Rigged up, slid pumping unit, pulled 1.5 rods, fished parted rod, pulled rods hooked to cheater pipe, 40 rods, pulled tubing, sanded bottom, went in.			
11-29-04 Checked hole sand at 3380', bailed 5 sacks, dug cellar, tore head down, set floor, pulled slips, ripped 2201', worked pipe, no gain, ripped 2018', pipe parted 550', ripper got stuck coming out, went in.			
11-30-04 Cut sand line, pulled pipe, cut ripper out, ran tubing to 1100', pumped 50 sacks, pulled to 700', pumped 35 sacks, pulled to 300', circulated to surface, pulled tubing, tore down, loaded out, filled cellar in.			
Subtotal			\$4,594.00
Sales Tax (6.3%)			\$289.42
Total			\$4,883.42

RECEIVED
DEC 18 2005
OCC WICHITA

COPELAND

Acid & Cement



POST OFFICE BOX 438
 HAYSVILLE, KS 67060
 (316) 524-1225
 (316) 524-1027 FAX

INVOICE

BURRTON, KS
 (620) 463-5161
 FAX (620) 463-2104

GREAT BEND, KS
 (620) 793-3366
 FAX (620) 793-3536

INVOICE NUMBER

0025811-IN

BILL TO: PROSPECT OIL & GAS CORP.
 PO BOX 837
 RUSSELL

KS 67665

LEASE:

FREEMAN 5

DATE	ORDER	SALESMAN	ORDER DATE	PURCHASE ORDER	SPECIAL INSTRUCTIONS	
11/30/04	25811		12/02/04			
QUANTITY	U/M	ITEM NO/DESCRIPTION		D/C	PRICE	EXTENSION
1.00	EA	PUMP TRUCK FOR P+A		.00%	450.00	450.00
40.00	MI	PUMP TRUCK MILEAGE		.00%	2.50	100.00
175.00	SAX	60-40 POZ MIX 4% GEL		.00%	6.25	1,093.75
3.00	SK	GEL		.00%	9.50	28.50
4.00	SAX	HULLS		.00%	25.00	100.00
1.00	DIA	2 1/2 SWIVEL RENTAL		.00%	85.00	85.00
175.00	EA	BULK CHARGE		.00%	1.00	175.00
304.40	MI	BULK TRUCK - TON MILES		.00%	.85	258.74
1.00	EA	7% FUEL SURCHARGE		.00%	56.61	56.61

FUEL SURCHARGE IS NOT TAXABLE AND IS ADDED TO MILEAGE, PUMP AND OR DELIVERY CHARGES ONLY.

[Handwritten signature]
 12/14

RECEIVED
 APR 18 2005

KCC WICHITA

There will be a charge of 1.5% (18% annual rate) on all past due accounts.

Copeland Acid & Cement is a subsidiary of Gressel Oil Field Service, Inc.

Gressel Oil Field Service, Inc. reserves a security interest in the goods sold until the same are paid for in full and reserve all the rights of a secured party under the Uniform Commercial Code.

REMIT TO: P.O. BOX 438
 Haysville, KS 67060

NET INVOICE: 2,347.60
 SALES TAX: 33.71

COP-BUR

INVOICE TOTAL: 2,381.31

NET 30 DAYS

RECEIVED BY

KANSAS CORPORATION COMMISSION



Conservation Division
130 South Market, Suite 2078
Wichita, Kansas 67202-3801
316-337-6200
Fax: 316-337-6211
FEIN: 48-6029925

INVOICE
Customer Copy

Copy

Invoice Date: December 17, 2004

Invoice Number: 2005060945

PROSPECT OIL & GAS
PO BOX 837
RUSSELL

KS 67665

Fed ID:

Due Date: January 01, 2005

Order Number: 14373		Contact:		Order Date: December 17, 2004	
Item	Qty	Acct Code / Service Description	Details	Unit Price	Total
1	3467	505 / Well Plugging > 1077 feet	15-159-04298-00-00 FREEMAN 5 330 FSL 2310 FWL 4-21-6W RICE QUALITY WELL SERVICE, INC.	\$0.0325	112.68
<i>KCC Contact: MONTGOMERY, BARBA.</i>			Order Subtotal:	\$112.68	

IMPORTANT!!!
*Please Return One Copy of Invoice
with Your Payment
in Order to Insure Correct Credit to Your Account.*

Order Total: \$112.68
Shipping Charges: 0.00
Invoice Total: \$112.68

3314
15

RECEIVED
APR 18 2005
KCC WICHITA

F12/4
[Signature]