

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20023-00-00
Spot: NENENE Sec/Twnshp/Rge: 9-3S-41W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: RUDOLPH WALTER Well #: 2
County: CHEYENNE Total Vertical Depth: 4775 feet

Operator License No.: 33019
Op Name: ROSEWOOD RESOURCES, INC.
Address: 2711 N. HASKELL - SUITE 2800, LB #22
DALLAS, TX 75204

PROD Size: 4.5 feet: 4767 w/175 sxs cmt
SURF Size: 8.625 feet: 300 w/325 sxs cmt

#155¹⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/24/2005 8:30 AM
Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.
Proposal Rcvd. from: TOM ROELFS Company: TR SERVICE AND RENTAL, INC. Phone: (785) 332-0374

Proposed Plugging Method: Ordered 275 sxs common cement - 10% gel - 250# hulls.
Plug through casing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/24/2005 10:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 300' w/325 sxs cement.
4 1/2" production casing set at 4767' w/175 sxs cement.
TD 4775'.
Connected to 4 1/2" production casing - pumped 208 sxs cement with 200# hulls.
Max. P.S.I. 725#. S.I.P. 725#.
Connected to 8 5/8" surface casing - pumped 58 sxs cement with 50# hulls.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
4665	4669		

RECEIVED
JUN - 1 2005
KCC WICHITA

Remarks: LONGHORN CEMENT COMPANY.

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

INVOICED
DATE 6-1-05
BILL NO. 2005061656

Form CP-2/3

MAY 25 2005

SHAKESPEARE OIL CO., INC.
BOX 669, SALEM, ILL.

#2 RUDOLPH WALTER

9-3-41W
NE NE NE

CONTR MURFIN DRILG. CO. CTY CHEYENNE

GEOL _____ FIELD CHERRY CREEK CONE

E 3610 KB CM 9/4/76 CARD ISSUED 11/4/76 IP P 28 BOPD + 1 1/2 BWPD
LKC 4665-69

+	+	+
+	+	+
+	+	+

API 15-023-20,923

LOG	TOPS	DEPTH	DATUM
ADM		4274	- 664
TOP		4320	- 710
OREAD		4395	- 785
LKC		4527	- 912
ORTH ZN		4664	-1054
RTD		4775	-1165

8-5/8" 300/325sx, 4 1/2" 4767/175sx
ø (1) 4660-19
DST (1) 4645-84/30-30-30-30, 360' sg &
MCO, SIP 400-400# FP 88-163# 175-
213#
MICT - CO & PF 4665-69 A 2500, REC LD
POP,

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

430105