

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-01451-00-00  
Spot: SENWSE Sec/Twnshp/Rge: 26-12S-22W  
1650 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: OGALLAH Well #: 4-2  
County: TREGO Total Vertical Depth: 4014 feet

Operator License No.: 6569  
Op Name: SCHMITT, CARMEN, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 3993 UNKNOWN  
SURF Size: 8.625 feet: 235 UNKNOWN

#130<sup>46</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/24/2005 8:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-5100

Proposed  
Plugging  
Method:

Plugging Proposal Received By: ROGER MOSES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/24/2005 11:40 AM KCC Agent: ROGER MOSES

**Actual Plugging Report:**

Ran tubing to 2173' - spotted 100 sxs cement with 300# hulls.  
Pulled tubing to 1070' - circulated with 100 sxs cement and 300# hulls.  
Pulled all tubing - squeezed 5 1/2" casing with 100 sxs cement.  
Tied to 5 1/2" x 8 5/8" annulus - squeezed with 5 sxs cement.  
Max. P.S.I. 1000#. S.I.P. 1000#.  
Total of 305 sxs 60/40 pozmix - 10% gel and 600# hulls.

**Perfs:**

Top	Bot	Thru	Comments
3988			OPEN HOLE

**RECEIVED**  
**JUN - 1 2005**  
**KCC WICHITA**

Remarks: LEASE ALSO KNOWN AS SCHOENTHALER #2. ALLIED CEMENTING COMPANY. STEWART TANK & BLACKHAWK TANK-WATER.

Plugged through: TBG

District: 04

*Handwritten initials*

Signed Roger L. Moses  
(TECHNICIAN)

**INVOICED**

DATE 6-1-05

INV. NO. 2005061658

**MAY 26 2005**

26-12-22W


PYRAMID DRILLING CO. # 2 SCHOENTHALER SE NW SE

Contr. \_\_\_\_\_ TREGO \_\_\_\_\_ County

E 2336 Comm. \_\_\_\_\_ Comp. 8-31-51 IP 381 BOPD (ARB)  
PHY POT

Tops	Depth	Datum	Casing
ANH	1738	598	8" 235 5" 3993
LANS	3604	-1268	
ARB	3991	-1655	OGALLAH POOL
T.D.	4014	-1678	

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS



26-12-22W