

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20024-00-01
Spot: NWSESESE Sec/Twnshp/Rge: 4-3S-41W
440 feet from S Section Line, 440 feet from E Section Line
Lease Name: ROBERT WALTER Well #: 1
County: CHEYENNE Total Vertical Depth: 4790 feet

Operator License No.: 33019
Op Name: ROSEWOOD RESOURCES, INC.
Address: 2711 N. HASKELL - SUITE 2800, LB #22
DALLAS, TX 75204

PROD Size: 4.5 feet: 4785 175 SX CMT
SURF Size: 8.625 feet: 260 225 SX CMT

A 155⁶⁸

Well Type: EOR UIC Docket No: E26882.1 Date/Time to Plug: 05/20/2005 7:30 AM
Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.
Proposal Rcvd. from: TOM ROELFS Company: TR SERVICE AND RENTAL, INC. Phone: (785) 332-0374

Proposed Plugging Method: Ordered 250 sxs common cement - 10% gel - 250# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/20/2005 10:15 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 260' w/225 sxs cement.
4 1/2" production casing set at 4785' w/175 sxs cement.
TD 4790'.
3 1/2" tubing cemented in 4 1/2" casing from surface to 4383'.
Connected to 3 1/2" tubing - pumped 190 sxs cement with 200# hulls.
Max. P.S.I. 480#. S.I.P. 300#.
Connected to 8 5/8" surface casing - pumped 28 sxs cement with 50# hulls.
Max. P.S.I. 310#. S.I.P. 280#.

Perfs:

Top	Bot	Thru	Comments
4672	4678		

RECEIVED
JUN - 1 2005
KCC WICHITA

Remarks: LONGHORN CEMENT COMPANY-TICKET #252.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

INVOICED
DATE 6-1-05
INV. NO. 2005061656

Form CP-2/3

MAY 23 2005

SHAKESPEARE OIL CO., INC. #1 ROBERT WALTER 4-3-41W
 P.O. BOX 669 SALEM, ILL. 440 FSL &
 CONTR MURFIN DRILG. CO. CTY CHEYENNE 440 FEL

GEOL _____ FIELD CHERRY CREEK

E 3622 KB CM 9/13/76 CARD ISSUED 10/28/76, P 95 BOPD + 3 BWPD
 LKC 4672-78

+	+	+
+	+	+
+	+	+

API 15-023-20,024

LOG TOPS	DEPTH	DATUM
NIOB	1468	+2154
B SC	3513	+ 109
ADM	4074	- 452
HOW	4282	- 660
TOP	4324	- 702
DR CREEK	4367	- 745
OREAD	4402	- 780
LANS 1A1	4470	- 848
LANS 1B1	4528	- 906
LANS 1C1	4586	- 964
LANS 1D1	4634	-1012
LANS 1E1	4670	-1048
LANS 1F1	4734	-1112
LANS 1G1	4764	-1142
BKC	4780	-1158
RID	4790	-1168

8-5/8" 260/225sx, 4 1/2" 4785/175sx

OST (1) 4645-84/30-30-30-30, REC 361'
 SG&MCO, SIP 400-400#, FP 88-163#;
 175-213#

MICT - PF 4672-78, A 500, REC LD, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

MAOICEN
 11/11/76