

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20020-00-01
Spot: SWSWSW Sec/Twnshp/Rge: 3-3S-41W
440 feet from S Section Line, 4840 feet from E Section Line
Lease Name: MARVIN ORTH Well #: 3
County: CHEYENNE Total Vertical Depth: 4770 feet

Operator License No.: 33019
Op Name: ROSEWOOD RESOURCES, INC.
Address: 2711 N. HASKELL - SUITE 2800, LB #22
DALLAS, TX 75204

PROD Size: 4.5 feet: 4759 w/175 sxs cmt
SURF Size: 8.625 feet: 291 w/225 sxs cmt

#155⁰³

Well Type: EOR UIC Docket No: E18584.2 Date/Time to Plug: 05/19/2005 3:00 PM
Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.
Proposal Rcvd. from: TOM ROELFS Company: TR SERVICE AND RENTAL, INC. Phone: (785) 332-0374

Proposed Plugging Method: Ordered 150 sxs of common cement - 10% gel - 200# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2005 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 291' w/225 sxs.
4 1/2" production casing set at 4759' w/175 sxs.
TD 4770'.
2 3/8" tubing cemented in 4 1/2" casing from surface to 4476'.
Connected to 2 3/8" tubing - pumped 97 sxs cement.
Max. P.S.I. 425#. S.I.P. 100#.
Connected to 8 5/8" surface casing - pumped 10 sxs cement.
Max. P.S.I. 500#. S.I.P. 425#.

Perfs:

Top	Bot	Thru	Comments
4675	4679		

RECEIVED
JUN - 1 2005
KCC WICHITA

Remarks: LONGHORN CEMENT COMPANY-TICKET #251.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

100
INVOICED
DATE 6-1-05
INV. NO. 2005061656

MAY 20 2005

SHAKESPEARE OIL CO.
BOX 669, SALEM, ILL.

#3 MARVIN ORTH

3-3-41W
440' FSL &
440' FWL, SW

CONTR MURFIN DRUG CO.

CTY CHEYENNE

GEOL

FIELD CHERRY CREEK CONF

E 3623 KB CM 8/17/76 CARD ISSUED 10/7/76

IP P 84 BOPD + 16 BWPD
LKC 4675-79

API 15-023-20,020

LOG	TOPS	DEPTH	DATUM
NIOB		1462	+2161
SC		3518	+ 105
ADM		4076	- 453
HOW		4289	- 666
TOP		4328	- 705
DR CRK		4374	- 751
OREAD		4404	- 781
LKC		4476	- 853
RUEB_ZN		4530	- 907
ORTH_ZN		4672	-1049
BKC		4782	-1159
RID		4770	-1147

8-5/8" 291/225SX, 4 1/2" 4759/175SX
DST (1) 4644-92/60-30-60, 1115' GIP,
450' CGO, 60' MCO, 50' HOCM, 180'
HOC SW, 390' OCSW, SIP 658#, FP
183-113#
MICT - PF (LKC) 4675-79, SWB 7BOPH,
TR W/6HRS, SD/16HRS, FU 1200' O, SWB
78FPH, 5%W/4HRS, NAT, POP

-	+	+	+
-	+	+	+
-	+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

430 0741