

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20128-00-01
Spot: E2SESW Sec/Twnshp/Rge: 3-3S-41W
660 feet from S Section Line, 2970 feet from E Section Line
Lease Name: MARVIN ORTH Well #: 5
County: CHEYENNE Total Vertical Depth: 4683 feet

Operator License No.: 33019
Op Name: ROSEWOOD RESOURCES, INC.
Address: 2711 N. HASKELL - SUITE 2800, LB #22
DALLAS, TX 75204

PROD Size: 4.5 feet: 4675 w/100 sxs cmt
SURF Size: 7.625 feet: 290 w/180 sxs cmt

\$ 152²⁰

Well Type: EOR UIC Docket No: E18584.3 Date/Time to Plug: 05/19/2005 9:00 AM
Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.
Proposal Rcvd. from: TOM ROELFS Company: TR SERVICE AND RENTAL, INC. Phone: (785) 332-0374

Proposed Plugging Method: Ordered 400 sxs common cement - 10% gel - 200# hulls.
Plug through casing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2005 2:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

7 5/8" surface casing set at 290' w/180 sxs.
4 1/2" production casing set at 4675' w/100 sxs.
TD 4683'.
2 7/8" tubing cemented in 4 1/2" casing from 500' to 3820'.
Connected to 4 1/2" casing - pumped 200 sxs cement with 150# hulls.
Max. P.S.I. 450#. S.I.P. 200#.
Connected to 7 5/8" surface casing - pumped 48 sxs cement.
Max. P.S.I. 300#. S.I.P. 125#.

Perfs:

Top	Bot	Thru	Comments
4636	4656		
4498	4504		
4442	4446		
4426	4434		

RECEIVED
JUN - 1 2005
KCC WICHITA

Remarks: LONGHORN CEMENT COMPANY-TICKET #250.

Plugged through: CSG

District: 04

Signed

Darrel Dipman
(TECHNICIAN)

INVOICED

DATE

6-1-05

TIME

200506056

Form CP-2/3

MAY 20 2005

