

X
4-100543

Copy

TO:

API number: 15-163-21,506-0001

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, ROOM #2078
WICHITA, KANSAS 67202-3802

S2
~~S2 N2~~ SW NW /4 SEC: 03-07-19 W
2280 Feet from N (N/S) Line
660 Feet from W (E/W) Line

Operator License 07076

LEASE: Noland WELL # 1 OWWO

Operator: Black Diamond Oil, Inc.

County: ROOKS

Address: P.O. Box 641
Hays, KS 67601

Well total Dept 1628 feet
Conductor Pipe _____ inch @ _____ feet
Surface pipe 8 5/8 inch @ 291 feet

Aband. Oil Well _____ Gas Well _____ Input Well _____ SWD: _____ D & A: X

Plugging contractor: Lawbanco Drilling License #: 5900

Address: _____

Company to plug at: _____ Hour: _____ Day: _____ Month: _____ Year: _____

Plugging proposal received from Ken Veghie

Company: Black Diamond Oil Phone: _____ RECEIVED KANSAS CORPORATION COMMISSION

Were:
1st plug @ 1628' with 20 sx
2nd plug @ 875' with 80 sx
3rd plug @ 350' with 40 sx
4th plug @ 40' with wiper plug and 10sx
Rat hole - 10 sx
SEP 12 2000
SEP 12 2000
CONSERVATION DIVISION
WICHITA, KS

Plugging proposal received by: David Wann
Pluggings operations attended by agent? All [], Part [], None [X]

Completed Hour: 6:15 PM Day: 15, Month: March Year: 1983

Actual plugging report:
Hole plugged as above. Order 160 sacks of 50/50 Posmix w/4% gel and 3% CC. The original plugging report was never filed. Well was plugged in 1983.

Remarks: Elevation: 2019 GL, Anhydrite top: 1553 feet Anhy. plug: Y

Dakota plug: Y Bottom plug in plac N

Plugged through drill pip Y

Arbuckle top Cemented by: Allied Cementing

I did [] did NOT [X] observe the plugging

David Wann
David Wann P.I.R.T. III
(agent)

BLACK DIAMOND OIL, INC.

217 E. 32ND, #A
HAYS, KS 67601

#1 NOLAND 'OWWO'


3-7-19W
2280' FNL &
660' FWL, NW/4

CONTR LAWBANCO DRILLING

CTY ROOKS

GEOLOGICAL

FIELD LOCUST GROVE EXT
(1/8 NE)



ELV 2024 KB SPD 3/12/83 CARD ISSUED

4/14/83

IP D&A/ARB
3/14/83

API 15-163-21,506-A

LOG	Tops	Depth/Datum
SC	1553 + 471
HEEB	3184-1160
TOR	3207-1183
LANS	3225-1201
BKC	3440-1416
ARB	3492-1468
RTD	3500-1476

OLD INFO: OPERATOR WAS PETX PETROLEUM CORPORATION, #1 NOLAND, SPD 11/29/81, SET 8 5/8 " 291 / 185 SX, COMP. AS D&A / ARB 12/7/81, (CARD ISSUED 4/1/82), CONTR: KISSINGER DRILLING

DST (1) 3220-3260 (LKC) / 30-30-30-30, REC 10' O SPTD M, SIP 105-62#, FP 42-42 / 42-42#, HP 1698-1698#

DST (2) 3297-3337 (LKC) / 30-30-30-30, REC NA, SIP 850-839#, FP 222-316 / 432-506#, HP 1698-1698#

DST (3) INTV NA / MISRUN

DST (4) 3388-3492 (LKC) / 30-30-15-15, REC 30' O SPTD M, SIP 1993-1993#, FP 105-105 / 105-105#, HP 1993-1993#

DST (5) 3440-3500 (PENN, ARB) / 30-30-30-30, REC 60' OCM, SIP 105-101#, FP 63-52 / 63-63#, HP 1909-1909#

NEW INFO: RE-ENTERED 3/12/83, WSH DWN TO 1500', COULD NOT GET TO BTM, P&A

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS