

To: 6 090376  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

6-20-88 227  
API NUMBER 15- 163-23,004-00-00 R

NE, SEC. 14, T 7 S, R 19 W/EX  
2970 feet from S section line  
2310 feet from E section line

Lease Name Farr Well # 1  
County Rooks 114.11  
Well Total Depth 3511 feet  
Conductor Pipe: Size        feet  
Surface Casing: Size 8 5/8 feet 207

TECHNICIAN'S PLUGGING REPORT

Operator License # 3007  
Operator: Western Kansas Exploration  
Name & Address 2700 Oak  
Hays, Ks. 67601

Abandoned Oil Well        Gas Well        Input Well        SWD Well        U&A x

Other well as hereinafter indicated       

Plugging Contractor Western Kansas Drilling License Number 4083

Address Hays, Ks.

Company to plug at: Hour:        Day: 17 Month: June Year: 19 88

Plugging proposal received from Jim Manley

(company name) Western Kansas Drilling (phone)       

were: Order 205 sks 60/40 Poz 6% Gel and 8 5/8" wiper plug. Spot all plugs through drill pipe w/heavy mud between all plugs.

       Plugging Proposal Received by Edwin A. Schumacher  
(TECHNICIAN)

Plugging Operations attended by Agent?: All        Part        None x

Operations Completed: Hour 1:00 PM Day: 20 Month: June Year: 19 88

ACTUAL PLUGGING REPORT 1st plug 3470' w/20 sks  
2nd plug 1460' w/20 sks  
3rd plug 855' w/100 sks  
4th plug 257' w/40 sks  
5th plug 40' wiper plug and 10 sks  
15 sks in rat hole

Remarks: Elevation 1955' Anhydrite 1449' Arbuckle- 3470'  
(If additional description is necessary, use BACK of this form.)

Jul 6, 1988

**INVOICED**

DATE 7-13-88

INV. NO. 21291  
6-20

AUG 3 1988 SEP 12 1988

Signed Edwin A. Schumacher  
(TECHNICIAN)

Edwin A. Schumacher FORM CP-2/3 Rev. 01-84

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... 06/15/88 month day year

API Number 15-163-23,004-00-00

OPERATOR: License # 3007 Name WESTERN KANSAS EXPLORATION Address 2700 Oak City/State/Zip HAYS 67601 Contact Person Stan Younger Phone (913) 628-2296

SW SW NE Sec. 14 Twp. 7 S, Rg. 19 East XX West 2970 Ft. from South Line of Section 2310 Ft. from East Line of Section

CONTRACTOR: License # 4083 Name WESTERN KANSAS DRILLING City/State HAYS, KANSAS 67601

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 330 feet County ROOKS

Well Drilled For: XX Oil Storage XX Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Lease Name FARR Well # 1 Ground surface elevation 1949 feet MSL Domestic well within 330 feet: yes XXno Municipal well within one mile: yes XXno Depth to bottom of fresh water 200 Depth to bottom of usable water 870

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Surface pipe by Alternate: 1 XX Surface pipe planned to be set 200 Conductor pipe required Projected Total Depth 3450 feet Formation ARBUCKLE

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 06/10/88 Signature of Operator or Agent Greg Indeman Title AS AGENT

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X 2 This Authorization Expires 6-12-10-88 Approved By DR 6-10-88

EFFECTIVE DATE: 6-15-88

SP 200' - Haul Water - Spud 6-11-88 SW SW NE Sec. 14 Twp. 7 S, Rg. 19 East XX West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth, TD/ANHY, Formation, and Feet of. Rows include 1st plug @ ft. deep, 2nd plug @ ft. deep, 3rd plug @ ft. deep, 4th plug @ ft. deep, 5th plug @ ft. deep, (2) Rathole to surface minus 5 feet, and (b) Mousehole to surface minus 5 feet.

NOTE: Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging. In Addition: Call district office before well is either plugged or production casing is cemented in. (Call 7 a.m. to 5 p.m. workdays)

District office use only: API #15-163-23,004 Surface casing of feet set with sxs at hours, 19 Alternate 1 or 2 surface pipe was used. Alternate 2 cementing was completed @ ft. depth with sxs on, 19 Hole plugged, 19, agent

RECEIVED STAT. CONSERVATION COMMISSION JUL 6, 1988 JUN 15 1988 JUN 17 1988 KCC District # Conservation Division Wichita, Kansas Form C-1 1186