

To: 6 031212
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT
Operator License # 5134

Operator: Graham Michaelis Corp
Name & Address Box 247
Wichita, Ks. 67201

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Chase, Ks.

Company to plug at: Hour: AM Day: 28 Month: Dec Year: 19 88

Plugging proposal received from Millard
(company name) Kelso (phone) _____

were: 8 5/8" set at 182' w/125 sks. 5 1/2" set at 3438' w/125 sks. Perf 3196' - 3388'. Order sand and common cement. Pull pipe. Order 200 sks 65/35 Poz 10% Gel 2% Dixel 500# Hulls
Applied Cement Co. B and L Water Trucks. Run wireline to anhy.

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1989

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:15AM Day: 28 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3140' w/5 sks common cement on sand w/bailer. Shots at 1525', 1215', and 1194'. Recovered 1194' of casing. Hole open to Anhy. Squeezed 8 5/8" w/200 sks cement w/500# Hulls mixed into max psi 600#. Close in psi 300#. Plug complete.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 1-19-89
INV. NO. 23688

Sub. 5

12-28
API NUMBER 15-163-01800-0000
C N/2 SW SW SEC. 4, T. 7 S, R. 19 W/E
990 feet from S section line
4620 feet from E section line
Lease Name Riffe Well # A 3
County _____ Rooks 114.14
Well Total Depth 3512 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 182

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow