

15163-01799-050272-28

6 031211

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

NW SE SW, SEC. 4, T 7 S, R 19 W/E
990 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Lease Name Riffe Well # A-1

Operator: Graham Michaelis Corp
Name & Address: Box 247
Wichita, Ks. 67201

County Rooks 113.82
Well Total Depth 3502 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 177

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: AM Day: 28 Month: Dec Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) _____

were: 8 5/8" set at 177' w/125 sks. 5 1/2" set at 3501' w/125 sks.

Perf 3214' - 3388'. Order sand and common cement. Pull pipe.

Order 200 sks 65/35 Poz 10% Gel 2% Dical 500# Hulls; Allied Cement Co.

B and L Water Truck. Run wireline to anhydrite.

RECEIVED
STATE CORPORATION COMMISSION
1-18-89
JAN 18 1989

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed at Wichita, Kansas Hour: 10:00AM Day: 28 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3160' w/5 sks common cement on sand w/bailer.

Recovered 32 joints 5 1/2" 1000' +. Hole open to anny. Squeezed 8 5/8" w/200 sks cement w/500# Hulls mixed into max psi 800#. Close in psi 400#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 1-19-89
INV. NO. 23686

Jub.S

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow