

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

15-163-19079-00-00  
API NUMBER ~~15-163-21185-0001~~

SE-4, Sec. 4, T 7 S, R 19 W/E  
\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # \_\_\_\_\_

Lease Name Livingston Well # 3  
*add  
1cc-211  
6-305*

Operator: J.L. King Oil Operations  
Name & Address: Box 73  
Russell, Kansas  
67665

County Rooks  
Well Total Depth 3471 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8" feet 188' - circ emt.

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing License Number \_\_\_\_\_

Address Russell, Kansas 67665

Company to plug at: Hour: AM Day: 26 Month: 10 Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Elmer Froelich

(company name) J.L. King Oil Oper. (phone) \_\_\_\_\_

were: 8 5/8" @ 188' w/ circ emt. - 5 1/2" @ 3471'

no record of pups - Pipe collapsed @ 1105'  
drilled to 1145' - was outside of pipe -  
Ordered 500-px 50 pps mix 6 Bagel - 8 shells.

Signed Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30pm Day: 26 Month: 10 Year: 19 82

ACTUAL PLUGGING REPORT Ran tbg to 1145' circ emt. w/ 350-px

to top - pulled tbg - Hook-up to annulus  
pumped 150-px in 8 5/8" w/ max PSI 800# -  
Hooked-up to 5 1/2" CSG and pumped an additional  
50-px emt. - PSI. to 1500# : total emt used was  
300-px in 5 1/2" - 1500# PSI.  
150-px in 8 5/8" - 850# PSI.

Remarks: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 08 1982  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

11-8-82

INVOICED

DATE 11-23-82  
INV. NO. 1685-W

Signed Dennis L. Hamel  
(TECHNICIAN)