

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24824-00-00
Spot: S2N2N2SW Sec/Twnshp/Rge: 24-17S-14W
2152 feet from S Section Line, 1295 feet from W Section Line
Lease Name: PATTON CLARK Well #: 1
County: BARTON Total Vertical Depth: 3500 feet

Operator License No.: 33437
Op Name: SEDONA OIL & GAS CORPORATION
Address: 5646 MILTON, SUITE 221
DALLAS, TX 75206

SURF Size: 8.625 feet: 873

#113 75

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/05/2005 10:00 PM
Plug Co. License No.: 33006 Plug Co. Name: ACE DRILL-N INC.
Proposal Rcvd. from: LARRY Company: SEDONA OIL & GAS CORPORATIO Phone: (214) 368-6383

Proposed Plugging Method: Order 160 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 03/05/2005 11:15 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

Perfs:

1st. Plug at 3430' w/25 sxs.
2nd. Plug at 950' w/50 sxs.
3rd. Plug at 370' w/60 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

RECEIVED
JUN - 3 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Bruce D. Basye
(TECHNICIAN)

INVOICED

DATE

6-6-05

INV. NO.

2005061668

Form CP-2/3

JUN 02 2005