

6  
070293

API NUMBER 15-163-22, 605-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SW-NW-NE, SEC. 2, T. 7 S, R 19 W  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4290 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9747

Lease Name LOWRY Well # 1-2

Operator: UNIVERSAL RESOURCES, INC.  
Name & Address 1800 DENVER, NAT'L BANK  
PLAZA, DENVER, COLORADO.  
80202

County ROOKS 114.89

Well Total Depth 3535 feet

Conductor Pipe: Size 0 feet ✓

Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated TAG # 182

Plugging Contractor ABERCROMBIE DRUG. INC License Number 5422

Address WICHITA, KANSAS, 67202

Company to plug at: Hour: 6:00 PM Day: 13<sup>th</sup> Month: JAN Year: 19 85

Plugging proposal received from BILL CRAIG.

(company name) ABERCROMBIE DRUG. INC (phone) 316-262-1841

were: 8 5/8" 262 ET SP. CUL #185<sup>SK</sup> COMMON GEL - CA-CL - BY HALLIBURTON  
ORDER 220<sup>SK 50</sup> 50 FORMIX GEL - CA-CL - 1 FLAME AND 8 5/8" PING.

SPOT WITH DRILL STEM - RECONDITION HOLE (50VIS) HEAVY MUD BETWEEN ALL PLUGS.  
ARBuckle @ 3480' - NO CIRCULATION PROBLEMS, MUD-VIS 48. Weight 9.8.  
CHLORIDES 3000 ELV. 2000, ANH. 1520

Plugging Proposal Received by Marion Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:15<sup>PM</sup> Day: 13<sup>th</sup> Month: JAN Year: 19 85

ACTUAL PLUGGING REPORT ORDERED 220<sup>SK 50</sup> 50 FORMIX GEL - CA-CL - 1 FLAME 9 8 5/8" PING.

SPOTTED WITH DRILL STEM - RECONDITIONED HOLE - HEAVY MUD BETWEEN ALL PLUGS.  
1<sup>st</sup> PLUG @ 3450 #125<sup>SK</sup> CNT - 2<sup>ND</sup> PLUG @ 1530 FT #125<sup>SK</sup> CNT.  
3<sup>RD</sup> PLUG @ 900 FT #100<sup>SK</sup> CNT #4<sup>SK</sup> SLAKE, 4<sup>TH</sup> PLUG @ 270 FT #50<sup>SK</sup> CNT.  
5<sup>TH</sup> PLUG HALL'S BRIDGE PLUG @ 40 FT #0 #10<sup>SK</sup> CNT, 10<sup>SK</sup> RAT HOLE (OVERLINED)  
Cemented by Halliburton CNT.

STATE CORPORATION COMMISSION  
JAN 17 1985  
JAN 17 1985

Remarks: (If additional description is necessary, use BACK of this form.)

I (do / did not) observe this plugging.

Signed Marion Schmidt 10  
(TECHNICIAN) 1-16-85  
Edic mgf