

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20036-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1967
11-17-67
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Marx Well No. 1

Location NW-SW-SE Sec. 24 Twp. 6 Rge. (E) (W) 26

County Sheridan Total Depth 3939'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box # 364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 11:30AM Day 2 Month 11 Year 1967

The above well was plugged as follows:

318'--7" OD Surface pipe, cement circulated with 115 Sx. (6 1/4" hole).
3938'--4 1/2" Production casing cemented on bottom with 100 Sx. Well Plugged back to
3906'. Top perforations from 3832' to 3835'.

Sanded well back to 3820' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing
and squeezed well with 7 sacks gel with 5 sacks hulls in gel and followed with 65 Sx.
cement from 1125' to 800' then 7 sacks gel from 800' to 325' and followed with 15 Sx.
cement from 325' to 250' then 3 sacks gel from 250' to to 30' and 5 Sx. cement from
30' to bottom of cellar. Maximum Pump-in pressure--400#. Final shut-in pressure--
300#. (Recovered 1125' 4 1/2" casing) (Mudding and cementing by Halliburton Company).

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11/17/67
INV. NO. 6698-W

Signed: A. S. P. Jekels
Well Plugging Supervisor