

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-19000-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1971
CONSERVATION DIVISION
Wichita, Kansas

4-13-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name A. L. Abercrombie, Incorporated,

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Vahling Well No. 2

Location SW-NW-SW Sec. 24 Twp. 6 Rge. (E) (W) 26

County Sheridan Total Depth 4114'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Santa Fe Pipe and Supply, Incorporated,

Address Box #562, Great Bend, Kansas. License No. 574

Operation Completed: Hour 1:00 PM Day 6 Month 4 Year 1971

The above well was plugged as follows:

3411'--8 5/8" Surface casing, cement circulated with 260 Sx. (6 3/4" Hole).

4095'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 4082'. Top perforations @ 3857'.

Pushed plug to 3800', sanded back to 3775' and set 3 Sx. cement with dump bailer.

Pulled 4 1/2" casing and squeezed well initially with 4 sacks hulls and 14 sacks gel

then 80 Cu. Ft. cement from 1325' to 1000' then 10 sacks gel from 1000' to 375' and

followed with 70 Cu. Ft. cement from 375' to 275' then 6 sacks gel from 275' to 35'

and finally 10 Cu. Ft. cement from 35' to bottom of cellar. Maximum pump-in pressure-

200#. Final shut-in pressure-150#. (Mudding and cementing by Sun Cementing).

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 4/13/71

INV. NO. 3539-W