

DISTRICT CONSERVATION AGENT'S REPORT

R

15-179-00195-00-00

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE NE SW

SEC. 24 TWP. 6 RGE. 26

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Vahling

Operator E. K. Carey, Contr. Address 200 E Ave Mc Pherson, Kans

Field \_\_\_\_\_ County Sheridan

Total Depth 3910 Feet.

Plugging Contractor same

Plugging Contractor's License No. \_\_\_\_\_

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 265' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at 700', displaced 20 sax cement through drill pipe, heavy mud to 200', set cementing plug and displaced 20 sax cement through drill pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

Edon Lett  
District Conservation Agent

Date 11-27-57

RECEIVED  
STATE CORPORATION COMMISSION  
12-4-57  
DEC 4 1957  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 24 T 6 R 26  
BOOK PAGE 64 LINE 45