

KANSAS

Form CP-3  
Rev. 6-4-68

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

13-065-20588-00-01

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217RECEIVED  
STATE CORPORATION COMMISSION  
DEC 27 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
12-27-72

Operator's Full Name Bonald C. Slawson,  
Complete Address 408 One-Twenty Building, Wichita, Kansas.  
Lease Name Klein Well No. B-1  
Location CSW-SE Sec. 19 Twp. 6 Rge. (E) (W) 25  
County Graham Total Depth 3855'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Slawson Drilling Company, Incorporated,  
Address 408 One-Twenty Bldg., Wichita, Ks. License No.         
Operation Completed: Hour 5:00 AM Day 23 Month 12 Year 1972

## The above well was plugged as follows:

330'--8 5/8" Surface casing, cement circulated with 200 Sx. (This well was drilled to the Anhydrite and surface casing set on it approximately 2 years ago by Cimarron Drillers).

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 110 Cu. Ft. cement thru DP from 1300' to 975'. Pulled DP to 340' and displaced 30 Cu. Ft. cement thru DP from 340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 12/27/72  
INV. NO. 6790-W