

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1970
CONSERVATION DIVISION
Wichita, Kansas
AUG 25/1970

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name McCauley Well No. 1

Location NE-NE-SE Sec. 16 Twp. 7 Rge. (E) (W) 19

County Rooks Total Depth 3420'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 5:00 AM Day 23 Month 8 Year 1970

The above well was plugged as follows:

225'--8 5/8" Surface casing, cement circulated with 150 Sx. (6 3/4" Hole).
Top of Dakota section @ 525'.

Circulated hole with heavy mud. Pulled DP to 750' and displaced 60 Sx. cement thru
DP from 750' to 450'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from 245'
to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 8/26/70
INV. NO. 2434-W