

R 15-163-02630-00-00

KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

SEP 4 1959
SEP 4 1959
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 62-25 County: _____ Rooks

Location: NW NW NW Sec. 16 Twp. 7 Rge. 19 (E) (W)

Name of Field: _____ Total Depth: 3490

I have this date completed supervision of plugging of:

Lease Name: Schruben Well No. 1

Operator's Full Name: Bennett & Roberts

Complete Address: Russell, Kans

Plugging Contractor: Southwest Casing Pulling Co

Address: Great Bend, Kans License No. 399

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 30 Month 8 Year 59

The above well was plugged as follows:

8 5/8" at 180' circulated with cement - 5 1/2" 3413' with 100 sax cement.

PB 3230' - perf 3222'.

Filled with sand to 3210', set 4 sax cement with dump bailer, pulled

approx 250' 5 1/2" to 600', circulated hole with heavy mud through 5 1/2"

(Gel Mud), displaced 20 sax cement through 5 1/2" at 600', heavy mud to 160'

displaced 20 sax cement through 5 1/2" at 160', heavy mud to 35', set

bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 12/21/59

INV. NO. 186-w