

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW NW NE

SEC. 16 TWP. 7 RGE. 19W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Mc Cauley

Operator Stearns Drg Co Address Russell, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3446 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 180' circulated with cement - 5 1/2" at 3446' with

150 sax cement behind - Lane Wells plugs to 3026' - perf at

3064' and squeezed at 3064' with 250 sax cement -

Filled hole with sand to 3040', set 4 sax cement with dump

bailer-pulled 200' 5 1/2" - filled hole with mud - Pumped

Halliburton cementing plug to 165', followed by 50 sax cement-

top of cement at 15' - filled to bottom cellar with cement by

hand -

Cementing by Halliburton Co

*E. J. ...*  
District Conservation Agent

Date 4-29-52

**PLUGGING**  
FILE SEC 16 TWP 7 RGE 19W  
BOOK PAGE 13 LINE 28

**RECEIVED**  
STATE CORPORATION COMMISSION  
MAY - 3 1952  
MAY 3 1952  
CONSERVATION DIVISION  
Wichita, Kansas

*F*