

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 109-15

LOCATION NW SE SE

SEC. 16 TWP. 7 RGE. 19

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Griebel

Operator Deep Rock Oil Corp Address Hutchinson, Kans

Field _____ County Rooks

Total Depth 3417 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 224' circulated with cement - 5 1/2" at 3417' with 75 sax
cement behind.

Lane Wells plugs to 3371', top perforations at 3301'.

Filled with chat to 3290', set 4 sax cement with dump bailer,

pulled 1340' 5 1/2", filled hole with mud to top, pumped cementing

plug to 325' followed by 39 sax cement, filling hole with cement

from 325 to 204', filled hole with mud to 40', set rock and 10 sax

cement to bottom cellar.

Mudding and Cementing by Halliburton Co.

RECEIVED
STATE CORPORATION COMMISSION
OCT 13 1951
OCT 13 1951

CONSERVATION DIVISION
Wichita, Kansas
[Signature]
District Conservation Agent

Date 10-10-51

PLUGGING
FILE SEC 16 T 7 R 19 W
BOOK PAGE 109 LINE 15