

KANSAS

AL

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 - 1970
12-08-70
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20001-00-01

Operator's Full Name Okmar Oil Company.
Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.
Lease Name Wente Well No. SWD-#1
Location SE-SE-NE Sec. 21 Twp. 6 Rge. (E) (W) 26
County Sheridan Total Depth 3925 RTD
Abandoned Oil Well Gas Well Input Well SWD Well X D & A
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling Company, Incorporated,
Address Box #364, Great Bend, Kansas. License No. 399
Operation Completed: Hour 12:15 PM Day 1 Month 12 Year 1970

The above well was plugged as follows:

321'--8 5/8" Surface casing, cement circulated with 175 Sx.
3925'--4 1/2" Production casing cemented on bottom with 185 Sx. Well plugged back to
3867. Top perforations from 3759' to 3761'.
Squeezed well initially with 5 sacks hulls and 8 sacks gel then 100 Sx. cement from
1300' to 975' then 17 sacks gel from 975' to 325' and followed with 25 Sx. cement from
325' to 250' then 5 sacks gel from 250' to 50' and finally 15 Sx. cement from 50' to
bottom of cellar. Maximum pump-in pressure- 400#. Final shut-in pressure--150 #.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. L. Dehala*
Well Plugging Supervisor

DATE 12/8/70
INV. NO. 3016-W