

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-30066-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
APR 13 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
4-13-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name A. L. Abercrombie, Incorporated,  
Complete Address 801 Union Center Building, Wichita, Kansas.  
Lease Name Vahling Well No. 3  
Location NE-NW-SW Sec. 24 Twp. 6 Rge. (E) (W) 26  
County Sheridan Total Depth 4283'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well X D & A         
Other well as hereafter indicated         
Plugging Contractor Santa Fe Pipe and Supply, Incorporated.  
Address Box #562, Great Bend, Kansas. License No. 574  
Operation Completed: Hour 4:30 PM Day 6 Month 4 Year 1971

The above well was plugged as follows:

334'--8 5/8" surface casing, cement circulated. (6 3/4" Hole).  
4163'--4 1/2" casing cemented on bottom with 175 Sx. Well plugged back to 3720'. Top perforations @ 3624'.  
Pushed plug to 3550', sanded well back to 3525' and set 3 Sx. cement with dump bailer.  
Pulled 4 1/2" casing and squeezed well initially with 4 sacks hulls and 14 sacks gel and followed with 80 Cu. Ft. cement from 1325' to 1000' then 10 sacks gel from 1000' to 375' and followed with 70 Cu. Ft. cement from 375' to 275' then 6 sacks gel from 275' to 35' and finally 10 Cu. Ft. from 35' to 0 Maximum pump-in pressure-200#. Final shut-in pressure-150#. (Mudding and cementing by Sun Cementing, Inc.O.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. G. Nichols  
Well Plugging Supervisor

DATE 4/13/71  
INV. NO. 3540-W