

15163 19083 0000

KANSAS

FORM CP-3
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- - ✓

245 North Water
Wichita, KS 67202

Operator's Full Name SOUTHERN STATES OIL COMPANY

Complete Address BOX 1365 - GREAT BEND, MANU. 67530

Lease Name CLARENCE HOLSMAN Well No. #1

Location SE-SE-SE Sec. 15 Twp. 7^S Rge. 19 (East) (West)

County ROOFS. Total Depth 3421^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor HELSO CASING PULLING

Address BOX 176 CHASE, MO. 67524 License No. 683

Operation Completed: Hour: 12:55^{PM} Day: 5 Month: DEC. Year: 1980

The above well was plugged as follows:

8 5/8" 194^{FE} SP. CML. w/125ST CNT. -> 5 1/2" SET AT 3408^{FE} w/150ST CNT.
PLUG-BACK. 3080^{FE} - PERFS - TOP 3276^{FE} - SHOT 4 TIMES - REC. 607^{FE}.
BOTTOM - (2) TWO CAST IRON PLUGS. SET AT. 3080^{FE} AND 3360^{FE}
ORDERED 140ST 50/150 PORMIX 6% GEL. -> 17ST GEL. -> 4ST HULL'S + 8 5/8" PLUG.
PUMPED IN 8 5/8" WITH PUMP TRUCK.
PUT IN - 3ST HULL'S - 12ST GEL. -> 70ST CNT. -> 5ST GEL. -> 1ST HULL'S
AND 70ST CNT. MAX. PRESSURE - 250^{LBS}

CEMENTED BY ALLIED CNT.

DEC 10 1980
12/10/80
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: Morgan Schmidt
Conservation Division Agent

INVOICED

DATE 1-12-81
INV. NO. 3861-W