

15163 19082 0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

AUG 19 1974
8/19/74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Southern States Oil Company

Complete Address Box 693, Great Bend, Kansas 67530

Lease Name Helzman Well No. 3

Location SE NE SE Sec. 15 Twp. 7 Rge. (E) (W) 19

County Reeks Total Depth 3538'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:30 P Day 16 Month 8 Year 1974

The above well was plugged as follows:

Total Depth 3538' 20 3/4 esg set at 200' ewe 175 sk.

7" esg set at 3440' ew 300 sk.

7" esg PBTB 3110' Perf. unknown.

Set 7" weed plug at 2800' -poured 20' sand -dumped 5 sk emt W/dump bailer.

Recovered 435' of 7" esg.

Pumped down 7" esg with 30 sk gel & water -150 sk emt W/100 lbs hulls.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/19/74

INV. NO. 9730-w

Signed: Leo F. Messer
Well Plugging Supervisor