

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-163- 20030-00-00

245 North Water  
Wichita, KS 67202

Operator's Full Name SOUTHERN STATES OIL COMPANY.

Complete Address P.O. BOX 1365 - GREAT BEND, MS. 67530

Lease Name BURTON Well No. #4

Location NE - <sup>SW</sup>SE - SW Sec. 14 Twp. 7<sup>S</sup> Rge. 19 (East) (West)

County ROOKS Total Depth 3397 FT.

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor HELSON CASING PULLING.

Address BOX 176 - CHASE, MS. 67524 License No. 683

Operation Completed: Hour: 10:40 AM Day: 5<sup>th</sup> Month: DEC Year: 1980

The above well was plugged as follows:

8 5/8" 200 FT SR. CUL -> 5 1/2" SET AT 3396 W/ 125 ST CMT.  
TOP OF PERFS 3248 FT DAMOTH BROKE IN SAND PLUGGED OFF BOTTOM.  
CASING PULLED INTO AT 800 FT RECOVERED 800 FT.  
PUMPED IN ANNULUS 10 ST HEAVY GEL MUD. + 25 ST GEL TO STOP FLOW.  
ORDERED 140 ST 50/50 POZMIK 6% GEL. 17 ST GEL. - 4 ST HULL'S - 7 7/8" PLUG.  
PUMPED IN WITH PUMP TRUCK.  
PUMPED IN 8 5/8" - 3 ST HULL'S - 12 ST GEL - 70 ST CMT. -> 5 ST GEL.  
1 ST HULL'S - RELEASED PLUG. AND 70 ST CMT. - MAX PRESSURE 150 LBS  
CEMENTED BY FILLED CMT.

I hereby certify that the above well was plugged as herein stated.

Signed: Marion Schmidt  
Conservation Division Agent

DEC 10 1980  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
DATE 1-12-80  
INV. NO. 3860-W