

f

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1977
CONSERVATION DIVISION
WICHITA, KANSAS
(of this well)
00-00

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -163-20597-
00-00

Operator's Full Name F & M Oil Company

Complete Address 505 Union Center, Wichita, Kansas 67202

Lease Name Riseley Well No. 1

Location SW NW SW Sec. 2 Twp. 3 Rge. (E) (W) 19

County Rooks Total Depth 3532'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering

Address Box 698, Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 11:15 A Day 16 Month 7 Year 1977

The above well was plugged as follows:

Total Depth 3532' 8 5/8 csg set 210' cwc 150 sk.

4 1/2 csg set 3331' cw 150 sk cem.

4 1/2 csg PBSD 3300' with perf. (3233'-3246')

Filled 4 1/2 csg W/sd (3300'-3200') dumped 4 sk cem W/dump bailer. (3200'-3170')

Cutoff & recovered 1800' of 4 1/2 csg.

Allied Cementing Co mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs

hulls, released cementing plug & pumped 140 sk 50-50 poz 6% & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: B. M. Mandy
Well Plugging Supervisor

DATE 7-19-77

INV. NO. 5512-W