

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-22,385 0000

LEASE NAME Livingston

WELL NUMBER 1

SPOT LOCATION SE/4 SW/4 SE/4

SEC. 4 TWP. 7S RGE. 19 ~~(E)~~ or (W)

COUNTY Rooks

Date Well Completed 6-6-84

Plugging Commenced 6-6-84

Plugging Completed 6-6-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR V & F Oil Company

ADDRESS Box 261, McPherson, Ks. 67460

PHONE # (316) 241-6630 OPERATORS LICENSE NO. 8942

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes If not, is well log attached? No logs run.

Producing formation N/A Depth to top \_\_\_\_\_ bottom T.D. 3550

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	301.36'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.


1st plug @ 3510' w/25 sx cement; 2nd plug @ 1560' w/25 sx cement;  
3rd plug @ 900' w/100 sx cement / 1 sx Cellulflake; 4th plug @ 320' w/50 sx cement;  
Bridge plug @ 40' w/10 sx cement, 10 sx cement in rathole

Cement was 50/50 pozmix, 6% gel/3% cc  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_  
Address Box 678, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF McPherson, ss.

Doug Van Loenen (employee of operator)  
(operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts and statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.



(Signature) Doug Van Loenen  
Doug Van Loenen  
(Address) Box 261, McPherson, Ks. 67460

SUBSCRIBED AND SWORN TO before me this 14th day of June, 1984

My Commission expires: 100.3.1985

[Signature]  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 15 1984  
16-15-84  
CONSERVATION DIVISION  
Wichita, Kansas