

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

JUN - 3 2005

Form CP-4
September 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC WICHITA

Lease Operator: Russell Oil, Inc.

Address: P.O. Box 1469 Plainfield, IL. 60544

Phone: (815) 608-7000 Operator License #: 3293

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Jay Pfiefer (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. 3500'

API Number: 15-009-24,324-00-06

Lease Name: Pflug

Well Number: 7

Spot Location (QQQQ): _____ NE - SW - SE

990 Feet from North / South Section Line

1650 Feet from East / West Section Line

Sec. 15 Twp. 19 S. R. 12 East West

County: Barton

Date Well Completed: _____

Plugging Commenced: 5-20-05

Plugging Completed: 5-23-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	387'	None
				5-1/2"	3499'	2010'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3100' and 5 sacks cement. Cut casing loose @2010', pulled up to 1450', pumped 100 sacks cement w/300# hulls, pulled up to 650', pumped 40 sacks cement w/100# hulls, pulled up to 250' and circulated 75 sacks cement to surface. 60/40 pos, 10% gel..Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Russell Oil, Inc.

State of Kansas County, Rice ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) *Mike Kelso*

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 2nd day of June, 2005

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bm