

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 6 Twp. 11 Rge. 20 (E) (W)

Location as "NE/CNW/SW" or footage from lines 900 ft. NS Line & 330 ft. WE Line NW 1/4

Lease Owner Herman Geo. Kaiser, Oil Producer

Lease Name Bieker Well No. 6

Office Address 909 Palace Bldg. Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed March 26 1957

Application for plugging filed March 26 1957

Application for plugging approved March 26 1957

Plugging commenced March 26 1957

Plugging completed March 26 1957

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3729 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	208	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud to 200 ft, set plug and cemented with 20 sacks cement and 1/3 sack hulls through drill pipe. Mudded hole to 40 ft., set plug and cemented with 10 sacks cement and 1/3 sack hulls to surface.

Name of Plugging Contractor H30, Inc. (If additional description is necessary, use BACK of this sheet)
Address 710 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. L. C. Sponenberg (employee of owner) or (owner/operator)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg

SUBSCRIBED AND SWORN TO before me this 29 day of March, 1957 (Address)

My commission expires February 13, 1960 Notary Public. Rose Jurey

PLUGGING
SEC 6 T 11 R 20W
BOOK PAGE 3 LINE 4

APR 4-1957

15-051-03553-00-00

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY Herman Geo. Kaiser

SEC. 6 T. 11 R. 20
 LOC. 900' NS Line and
 330' WE Line of NW¹/₄

FARM Bieker NO. 6

COUNTY Ellis

TOTAL DEPTH 3729'
 COMM. 3/15/57 COMP. 3/26/57
 SHOT OR TREATED
 CONTRACTOR H-30, Inc.
 ISSUED



CASING

20	10
15	8 208'
12	6
13	5

2074 K.B.
 ELEVATION 2069 G.F.

PRODUCTION D&A

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Sill and Shale	70
Sand	100
Clay and Sand	115
Blue Shale	350
Shale, Shells and Sand Streaks	1045
Sand	1210
Shale and Shells	1512
Anhydrite	1555
Shale and Shells	1860
Shale and Lime Streaks	2015
Shale and Lime	3349
Kansas City Lime	3560
Lime and Shale	3634
Shale, Conglomerate and Cherty	3700
Shale and Chert	3719
Arbuckle	3729

FORMATION TOPS

HEEBNER	3321'
LANSING	3358'
ARBUCKLE	3715'

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By L.C. Spruency

STATE OF KANSAS |
 | SS
 COUNTY OF SEDGWICK |

Subscribed and sworn to before me, a notary public, in and for said Co County and State this 28th day of March, 1957.

Rose Lurey
 Notary Public

My Commission expires February 13, 1960.

RECEIVED
 REGISTRATION COMMISSION
 APR 4, 1957
 APR 4 - 1957

PLUGGING
 FILE SEC 6 T. 11 R. 20W
 BOOK PAGE 3 LINE 4

OFFICE OF THE REGISTER
 WICHITA, KANSAS