

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

JUN - 6 2005

KCC WICHITA

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oxy USA, Inc.
Address: Box 2528 Liberal KS
Phone: (620) 629-4200 Operator License #: 5447
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 3-11-05 (Date)
by: Ken Jehlik & Mike Meier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Morrow Depth to Top: 4892 Bottom: 4911 T.D. 5000

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-055-10029-00-00
Lease Name: Tait C
Well Number: 6
Spot Location (QQQQ): _____ - _____ - NW - NW
660 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 27 Twp. 24 S. R. 33 East West
County: Finney
Date Well Completed: 10-29-62
Plugging Commenced: 3-14-05
Plugging Completed: 3-15-05

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1926	
				5 1/2	4994	602

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

5 1/2 was stuck @ 700 mixed 400 lb. hulls & 25 sx cmt. to plug perfs from 4883 to 4683, pumped 64 bbls. mud spacer to 2000, 25 sx 2000 to 1800, mud to 0. Shot 5 1/2 loose @ 602 Circ. hole w/mud, 55 sx cmt. 600 to 450 10 sx 40 to 0 Capped 8 5/8 3ft below G.C.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Oxy USA Inc.
State of Kansas County, Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Kenny Andrews
(Address) 1701 N. Kansas PO Box 2528 Liberal, KS. 67905

SUBSCRIBED and SWORN TO before me this 31 day of May, 2005
Anita Peterson My Commission Expires: Oct. 1, 2005
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bm