

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-249710000

LEASE NAME Richards

WELL NUMBER 6
4,950 Ft. from S Section Line

1,580 Ft. from E Section Line

SEC. 16 TWP. 20 RGE. 20 (E) or (W)

COUNTY Ellis

Date Well Completed 8-4-97

Plugging Commenced 8-4-97

Plugging Completed 8-4-97

LEASE OPERATOR Mai Oil Operations, Inc.

ADDRESS Box 33, Russell, Kansas

PHONE#(913) 483-2169 OPERATORS LICENSE NO. 5259

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-4-97 (date)

by Bruce B. Asye (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,710'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	224'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Fill hole w/heavy mud. Push bridge plug to 1,570', spot 25 sax cement on plug thru drill pipe. Push bridge plug to 780', spot 100 sax cement on plug thru drill pipe. Push bridge plug to 275', spot 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mai Oil Operations, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, SS.

Jack P. Beeman, Sec.-Treas. (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Shields Bldg. Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 12th day of August, 19 97

Ruth Phillips
Notary Public

My Commission Expires:

