

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

15-051-02343-00-00

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER Drlg. Completion date 1/27/57. (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Kaiser-Francis Oil Company OPERATOR'S LICENSE NO. 6568 *6/10*

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468 PHONE # (918) 494-0000

LEASE (FARM) Bieker WELL NO. 2 WELL LOCATION SW NW NW COUNTY Ellis

SEC. 6 TWP. 11S RGE. 20 (X) or (W) TOTAL DEPTH 3707 PLUG BACK TD 3629½

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 191 CEMENTED WITH 150 SACKS

CASING SIZE 5 1/2 SET AT 3707 CEMENTED WITH 125 SACKS

Note: 5½" csg. squeezed @ 1540' w/550 sxs cmt.

PERFORATED AT 3606 - 09

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Plugging procedure will be discussed with KCC district office prior to P & A. Suggest - pumping cement down 5½" casing as directed by district office.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? on old form (If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN To be scheduled upon approval.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Glenn Jackson, Supt. PHONE # (316) 564-3214

ADDRESS P. O. Box 666, Ellinwood, KS 67526

PLUGGING CONTRACTOR Kaiser-Francis Oil Company LICENSE NO. 6568 *6/10*

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468 PHONE # (918) 494-0000

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED:

C. Jan Palenberg
(Operator or Agent)

DATE:

2/12/90

④

COMPANY **Herman Geo. Kaiser & Francis Oil & Gas, Inc.**

SEC. 6 T. 11 R. 20W

LOC. SW NW NW 1/4

FARM **Bieker**

NO. **2**

TOTAL DEPTH **3707**

COUNTY **Ellis**

COMM. **1/13/57**


COMP. **1/27/57**

KANSAS

SHOT OR TREATED

CONTRACTOR **H-30, Inc.**

ISSUED



CASING

20	10	
15	8	191'
12	6	
13	5	3707'

ELEVATION **2047 K.B.**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

River Sand	25
Gray Clay	70
Clay & Sand Streaks	120
Blue Shale	295
Shale, Clay & Sand Streaks	550
Shale & Sand Streaks	1130
Shale, Shells, & Red Bed	1256
Shale, Shells, & Sand Streaks	1485
Anhydrite	1538
Shale, Red Bed & Shells	1700
Shale & Shells	1920
Shale & Lime	3275
Lime, Shale & Chert	3345
Lime & Chert	3374
Lime	3405
Shale & Lime	3409
Lime	3524
Lime & Shale	3632
Shale Lime & Chert	3652
Arbuckle Lime	3695
Total Depth	3707

FORMATION TOPS

HEBNER	3275
LANSING	3312
BASE KANSAS CITY	3539
CONGLOMERATE	3569
SIMPSON	3591
ARBUCKLE	3608

RECEIVED
 STATE CORPORATION COMMISSION
 Feb 14 1960
 FEB 14 1960

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *C. C. Sprouber*

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 30th day of January, 1957.

Rose Fussey
 Notary Public

My Commission expires February 13, 1960.



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE
MAY 14 1990
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

February 14, 1990
NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Kaiser-Francis Oil Company
P.O. box 21468
Tulsa, OK 74121-1468

Bieker 2
SW NW NW
Sec. 06-11-20W
Ellis County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #4 2301 E. 13th
Hays, Ks 67601
(913) 628-1200