

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-151-21440-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date _____.

Well Operator: Kenneth S. White KCC License #: 30128
(Owner/Company Name) (Operator's)

Address: 2400 N. Woodlawn, Suite 115 City: Wichita

State: Kansas Zip Code: 67220 Contact Phone: (316) 682-6300

Lease: Frey Miller Well #: 1-5 Sec. 5 Twp. 26 S. R. 11 East West

W2 - NW - SE Spot Location / QQQQ County: Pratt

1320 1980 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1320 2040 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 307' Cemented with: 175 Sacks

Production Casing Size: 4-1/2" Set at: 4295' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4041-4056, 4075, 4077, 4087, 4089, 4097, 4099

Elevation: 1850 (G.L. / K.B.) T.D.: _____ P.B.T.D.: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Fill with sand to 3900' and dump 5 sacks cement, shoot casing for recovery, pull casing and plug @ 650' w/50 sacks cement, 70 sacks @ 275', 15 sacks @ 40', 60/40 PozMix, 6% gel

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Sent in when drilled

KANSAS CORPORATION COMMISSION
MAY 31 2005
RECEIVED

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Herb Durant Phone: (620) 886-5463

Address: P.O. Box 251 City / State: Medicine Lodge, KS 67104

Plugging Contractor: Mike's Testing & Salvage Inc. KCC License #: 31529

Address: P.O. Box 467, Chase KS 67524 Phone: (620) 938-2943

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 5/26/05 Authorized Operator / Agent: Kenneth S. White
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

White, Kenneth S.
2400 N. Woodlawn, Suite 115
Wichita, KS 67220

June 01, 2005

Re: FREYMILLER #1-5
API 15-151-21440-00-00
W2NWSE 5-26S-11W, 1980 FSL 2040 FEL
PRATT COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely



David P. Williams
Production Supervisor