

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 055-97416 ⁰⁰²⁵⁵⁻⁰⁰⁻⁰¹ (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date spud 11/29/58

Well Operator: XTO Energy, Inc. KCC License #: 32864
Address: 210 Park Ave, Suite 2350 City: Oklahoma City
State: Oklahoma Zip Code: 73102 Contact Phone: (405) 319 - 3212
Lease: Oldweiler Well #: 1 Sec. 26 Twp. 22 S. R. 32 East West
C - SE Spot Location / QQQQ County: Finney

1320 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
1320 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: N/A Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8" Set at: 209' Cemented with: 175 Sacks
Production Casing Size: 5 1/2" Set at: 2749' Cemented with: 750 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs 2690' - 2698' & 2723' - 2728'

Elevation: 2949' (G.L. / K.B.) T.D.: 2750' P.B.T.D.: 2747' Anhydrite Depth: Not available
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): CIBP @ 2640' w/ 2 sx cmt, 40 sx cmt @ csg cut 1000'+/-100'
plug 47.2 yld, 90 sx cmt @ 309' - 109' 106.2 yld, 10 sx cmt @ 34' - 4' 11.8 yld. Mud weight (min. 9 ppg) Cmt weight (min 16 ppg).

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Checked with Janice Martin in the KCC Library and was told that the ACO-1 form was not used back when this well was completed.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: David Littell Phone: (620) 355 - 7838

Address: 805 S. Hwy 25 City / State: Lakin, KS 67860

Plugging Contractor: Freeport Pipe & Supply Sargent+Horton Plugging Inc. KCC License #: 31151
(Company Name) (Contractor's)

Address: Rt. 1, Box 49BA, Tyrone, OK 73951 Phone: (580) 854 - 6406

Proposed Date and Hour of Plugging (if known?): approx. June 30, 2005

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 6/10/05 Authorized Operator / Agent: Karen Byers
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
JUN 13 2005
KCC WICHITA

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

XTO Energy Inc.
210 Park Avenue - Suite 2350
Oklahoma City, OK 73102

June 15, 2005

Re: OLDWEILER UNIT OWWO #1
API 15-055-00255-00-01
SE 26-22S-32W, 1320 FSL 1320 FEL
FINNEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely



David P. Williams
Production Supervisor