

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-24507-00-00  
Spot: W2SWSE Sec/Twnshp/Rge: 24-13S-20W  
660 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: BOSCHOWITZKI Well #: 1-24  
County: ELLIS Total Vertical Depth: 3800 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

PROD Size: 5.5 feet: 3799 w/100 sxs cmt  
SURF Size: 8.625 feet: 240 w/140 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/10/2005 9:30 AM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: DALE POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered 525 sxs 60/40 pozmix - 10% gel - 300# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/10/2005 3:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech shot two hole perfs at 650' - 1475' - 2050'.  
Poe Well Service RIH with tubing to 2110'.  
Allied rigged onto tubing and pumped 100 sxs 60/40 pozmix with 400# hulls mixed in.  
Pulled tubing to 1500' and pumped 200 sxs 60/40 pozmix with 400# hulls mixed in.  
Pulled tubing to 750' and pumped 65 sxs 60/40 pozmix.  
Pulled tubing to 378' and pumped 30 sxs 60/40 pozmix with 200# hulls mixed in to circulate cement into pit area.  
Pulled tubing and topped with 15 sxs - casing was standing full.  
Tied onto 8 5/8" casing and pumped 10 sxs 60/40 pozmix.  
Max. P.S.I. 400#. S.I.P. 300#.  
Used 420 sxs 60/40 pozmix and 1000# hulls.

Perfs:

Top	Bot	Thru	Comments
3788	3792		

Remarks: ALLIED CEMENTING COMPANY-TICKET #18709.

Plugged through: TBG

District: 04

Signed 

(TECHNICIAN)

JUN 13 2005

RECEIVED  
JUN 15 2005  
KCC WICHITA

Form CP-2/3

GENERAL OIL COMPANY, INC  
WICHITA, KS 67214

24-13 -20W  
C W/2 SW SE

#1-24 BOSCHOWITZKI

site: 1-3/4 S & 3 E OF ELLIS, KS

city: ELLIS

API 15-051-24507

contr: WOODMAN-IANNITTI DRILLING COMPANY

field: IRVIN

geol: DAVID BREWER


lr  
date 08/20/87

spd  
date 09/22/87

drig  
comp 09/29/87

card  
issued 01/13/88

last  
revised 01/13/88



Elv: 2035 KB LOG	
tops.....	depth/datum
ANH.....	1456 +579
HEEB.....	3412 -1377
TOR.....	3435 -1400
LANS.....	3457 -1422
BKC.....	3721 -1686
MARM.....	3745 -1710
ARB.....	3782 -1747
RTD.....	3800 -1765

**IP status:**

OIL, P 25 BOPD, NW, ARB 3788-3792,  
CSG: 8-5/8" 240 / 140 SX, 5-1/2" 3799 / 100 SX  
NO CORES  
DST (1) 3788-3800 (ARB), / 30-45-45-60, 120' GIP, REC  
830' CLEAN GSY OIL, 90' HG & MCO ISIP 1177# FSIP  
1133# IFP 88# -22# FFP 243# -353# IHP 2023# FHP  
1957# BHT 125 °  
MICT - CO, PF (ARB) 3788-3792, AC 200 GAL (15% NE),  
SWB DWN, SO, POP, P 25 BOPD, NW, 10/17/87

NOTE: CORRECTION: 9/23/87 - ORIGINALLY FIRST  
REPORTED IN NW SW SE

COPYRIGHT 1987  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS