

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22391-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 26-12S-18W  
1520 feet from S Section Line, 2540 feet from E Section Line  
Lease Name: HOLY CROSS Well #: 4  
County: ELLIS Total Vertical Depth: 3800 feet

Operator License No.: 6931  
Op Name: BOWMAN OIL COMPANY, A GENERAL  
Address: 805 CODELL RD.  
CODELL, KS 67663

PROD Size: 4.5 feet: 3799 200 SX CMT  
SURF Size: 8.625 feet: 208 140 SX CMT

#123<sup>50</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/25/2005 8:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: LOUIS "DON" BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed  
Plugging  
Method:

Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/25/2005 1:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing 2350' - 1400' - 725'.  
TIH with tubing to 2400' - mixed and circulated cement with 130 sxs cement with 400# hulls.  
POOH. Swaged onto 4 1/2" - circulated cement up 8 5/8" with 50 sxs.  
Shut in and pumped to pressure with 20 sxs cement.  
Max. P.S.I. 500#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3650	3770		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Jay Pfeifer*

(TECHNICIAN)

INVOICED

RECEIVED

DATE

10-13-05

JUN 13 2005

REF. NO.

2005061709

KCC WICHITA

Form CP-2/3

JUN 08 2005

replacement card

H & H LEASE OPERS  
HAYS KS

26-12S-18W  
1520'FSL & 2540'FEL, SEC

# 4 HOLY CROSS

site: 1-1/2 S & 5-1/4 E OF HYACINTH KS

by: ELLIS

API 15-051-22391

contr: DREILING OIL

field: HOLY CROSS

well:

Tr date 04/29/81    spo date 05/10/81    drtg comp 05/16/81    card issued 05/13/82    last revised 03/16/98


ELV: 2140 TOPO  
 tops.....depth/datum  
 RTD.....3690 -1550  
 NO TOPS RPTD

**IP status:**  
 OIL, LKC, ARB , INTV NA , 08/01/81  
 INFO RELEASED: 3/16/98 - WAS OIL WELL - TEMP  
 COMP  
 CSG: 8-5/8" 200+ , PROD CSG NA  
 COMMENT: REDESCRIBED LOC - IS ALSO 200'FSL &  
 100'FWL, SW NW SE  
 NO CORES OR DSTS RPTD  
 MICT - CO, PF (ARB) INTV NA, SWB WTR, W/SLI SO,  
 PF (LKC) INTV NA, AC'D, SO, POP, OIL WELL  
 (POTENTIAL NOT RPTD), 8/1/81, COMMINGLED - NO  
 OTHER INFO RELEASED BY OPERATOR OR ON KCC  
 RECORDS (NO ACO, NO PLUG RPT); ALL REQUESTS  
 FOR INFO DENIED