

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23013-00-00
Spot: E2NWN Sec/Twnshp/Rge: 5-9S-25W
4560 feet from S Section Line, 1740 feet from E Section Line
Lease Name: DREILING Well #: 1-5
County: GRAHAM Total Vertical Depth: 4026 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: P.O. BOX 1469
PLAINFIELD, IL 60544

PROD Size: 5.5 feet: 4019 135 SX CMT
SURF Size: 8.625 feet: 270 175 SX CMT

#130⁸⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2005 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7387

Proposed Plugging Method: Ordered out 280 sxs 60/40 pozmix - 10% gel - 300# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2005 5:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded off casing to 3780' and topped with 5 sxs cement with a dump bailer.
Cut casing at 2280' - would not come free - tied onto and tried to get an injection rate - not able to pump into.
Come up to 1325' and cut casing free and pulled up to 925'.
Mixed and pumped 100 sxs cement.
Pulled up to 250' and circulated cement with 65 sxs.
POOH. Hole full of cement.

Perfs:

Top	Bot	Thru	Comments
3844	3848		
3835	3839		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

INVOICED

DATE 6-13-05

INV. NO. 2005061711

RECEIVED
JUN 13 2005
KCC WICHITA

Form CP-2/3

JUN 08 2005

RUSSELL OIL
PLAINFIELD IL 60544

5-09S-25W
720' FNL & 1740' FEL, SEC

#1-5 DREILING

site: 2-1/2 S & 2-3/4 W OF MORLAND KS cy: GRAHAM AP# 15-065-23013
contr: SOUTHWIND DRILLING #1 field: KNOLL
geol: TODD E. MORGENSTERN
fr date 10/15/2004 spcl date 11/05/2004 drlg comp 11/13/2004 card issued 03/14/2005 last revised 03/14/2005

E.V: 2478 KB, 2468 GL SMP
tops.....depth/datum
ANH.....2172 +306
PBD3880 -1402
LTD.....4025 -1547
RTD.....4026 -1548
NO TOPS RPTD
LOGGED

IP status
D&A, MARM , 11/26/2004
CSG: 8-5/8" 270 / 175 SX (ALT 2), 5-1/2" 4019 / 135 SX, MULTI
STAGE COLLAR AT 2207 (NOT CMTD)
NO CORES
DSTS TAKEN - DETAILS NA
TRGT ZN: LKC (OIL), PTD 4100 (MARM), MICT - CO, FF
(LKC) 3835-3839, SWB DWN, NON-COMMERCIAL, SI -
EVAL, DECISION MADE TO P & A 11/26/2004 - TIGHT HOLE
- NO OTHER INFO AVAILABLE - TEMP COMP 3/14/2005