

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-193-20334-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 30-10S-32W  
990 feet from S Section Line, 990 feet from E Section Line  
Lease Name: CLOSE B Well #: 1  
County: THOMAS Total Vertical Depth: 4655 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

PROD Size: 4.5 feet: 4390 250 SX CMT  
SURF Size: 8.625 feet: 296' 225 SX CMT

#151<sup>29</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/26/2005 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: PAT CANADAY Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Plug through casing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/26/2005 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface pipe set at 296' w/225 sxs cement.  
4 1/2" production casing set at 4390' w/250 sxs cement.  
PBTD 4309'.  
DV tool set at 2572' w/700 sxs.  
Connected to 4 1/2" production casing - pumped 270 sxs cement with 600# hulls.  
Max. P.S.I. 600#. S.I.P. 500#.  
Connected to 8 5/8" surface casing - pumped 10 sxs cement.  
Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
4174	4288		

Remarks: LEASE FORMERLY KNOWN AS CLOSE #1. ALLIED CEMENTING COMPANY-TICKET #19243.

Plugged through: CSG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

INVOICED  
DATE 6-13-05  
INV. NO. 2005061714

RECEIVED  
JUN 13 2005  
KCC WICHITA

MAY 27 2005

CHIEF DRILLING COMPANY, INC. 905 CENTURY PLAZA BLDG. WICHITA, KS. 67202  
 CONTR WARRIOR DRILLING COMPANY CTY THOMAS  
 GEOL JIM GRIBI FIELD WC(U-PAC NORTH DISC)  
 REPLACEMENT CARD 30-10-32W NW SE SE  
 #1 CLOSE  
 ELV 3073 KB SPD 12/4/84 CARD ISSUED 3/28/85 IP P 135 BOPD, NW  
 3068 GL DRLG COMP 12/16/84 LKC 4205-4289 OA  
 API 15-193-20,334

+	+
+	+
+	+

LOG	Tops	Depth	Datum
ANII	2572	501	
B ANH	2598	475	
WAB	3632	559	
TOP	3760	687	
HEEB	3986	913	
TOR	4003	930	
LANS	4024	951	
MUN CR	4156	1083	
STARK	4242	1169	
BKC	4306	1233	
MARM	4343	1270	
PAW	4435	1362	
FT SC	4498	1425	
CHER SH	4527	1454	
JOHN ZH	4572	1499	

8 5/8 " 296 / 225SX, 4 1/2 " 4390 / 250SX  
 NO CORES  
 DST (1) 4045-4065 (LANS 35' ZN) / 30-30-45-60, REC 70' MW, SIP 1119-1119#, FP 44-53 / 80-80#  
 DST (2) 4093-4118 (LANS 70'-90' ZN) / 30-30-45-60, REC 345' W, SIP 1210-1210#, FP 71-125 / 133-214#  
 DST (3) 4150-4188 (LANS 120'-140' ZN) / 30-30-45-60, REC 1530' CLEAN GSY OIL, 870' W, SIP 1164-1164#, FP 267-580 / 625-867#  
 DST (4) 4187-4218 (MUN CR) / 30-30-45-60, 880' GIP, REC 140' HO & GCM (30% G, 30% OIL, 40% M), 60' HO CM (7% G, 53% OIL, 40% M), SIP 1300-1300#, FP 71-89 / 89-107#  
 DST (5) 4214-4238 (LANS 180' ZN) / 30-30-45-60, 120' GIP, REC 25' GCM, SIP 53-53#, FP 44-44# / FFP NA  
 PBTB ..... 4240-1167 LTD ..... 4059-1586  
 RTD ..... 4655-1582  
 INFO RELEASED: 7/3/86 - WAS OIL WELL - TIGHT HOLE  
 (over)

COPYRIGHT 1985  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

CHIEF DRILLING COMPANY, INC. #1 CLOSE 30-10-32W NW SE SE

DST (6) 4241-4271 (LANS 200' ZN) / 30-30-60-60, 470' GIP, REC 90' HO & GCM (10% G, 45% M, 45% OIL), SIP 894-894#, FP 53-62 / 71-80#  
 DST (7) 4273-4300 (LANS 220' ZN) / 30-30-45-60, 630' GIP, REC 120' CLEAN GSY OIL (GR 40%), 30' HO & GCM (15% G, 45% OIL, 50% M), SIP 607-446# & BLDG, FP 80-89 / 89-107#  
 DST (8) 4445-4489 (PAW) / 30-30-15-30, REC 10' M, W / OIL SPTS, SIP 53-53#, FP 44-44 / 44-44#  
 DST (9) 4545-4597 (JOHN ZN) / 30-30-15-30, REC 5' M, SIP 89-89#, FP 80-80 / 80-80#  
 MICT - GO, PF (LKC) 4284-4288, W / 4 SPF, AC 4750 GAL, PF (LKC) 4256-4260, W / 4 SPF, AC 250 GAL, PF (LKC) 4205-4209, W / 4 SPF, AC 250 GAL, GSO, T&R, POP, P 135 BOPD, NW (GR 37%), 1/23/85

RECEIVED  
 02/16/85