

6 010698

1-11

283
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-22, 204 0000

C SW SW, SEC. 21, T 7 S, R 19 W EX

1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5352

Lease Name Schneider Well # 7

Operator: Baird Oil Co. Inc.
Name & Address: Box 428
Logan, Ks. 67646

County Rooks 11096
Well Total Depth 3414 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 206

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Baird Oil Co. Inc. License Number 5352

Address Same

Company to plug at: Hour: 9:30AM Day: 11 Month: Jan Year: 19 90

Plugging proposal received from James Baird

(company name) Baird Oil Co. (phone)

were: Perf anhydrite at 1450'. Order 350 sks 65/35 poz 8% gel 2 sks f.c. 500#
hulls. 4 1/2" casing at 3407' Anhydrite 1446 - 76.

Elevation 1957. Top Dakota 557 to 857.

Plugging Proposal Received by D.F.B.
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:45AM Day: 11 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT Ran wireline to t.d. 3414. Shot anhydrite at

1450; holes in dakota at 800'. Pumped down 4 1/2" casing 250 sks cement 65/35 poz 8% gel 350#
hull. Max pres. 600#. Closed w/200#. Pumped down 8 5/8" s.p. 100 sks cementw/150# hulls.

Max pres 600#. Closed w/200#. Jim Baird Operator on location.

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1990

Remarks: (If additional description is necessary use BACK of this form.)

INVOICED

DATE FEB 05 1990

INV. NO. 27307

J.F.S.

Signed Dale F. Balthazor
(TECHNICIAN)

Dale F. Balthazor FORM CP-2/3
Rev. 01-84