

4-032078

7-27-95

API Number: 15-163-21,810 0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

SW SW NE /4 SEC. 21, 07S, 19 W  
2970 feet from S section line  
2310 feet from E section line

Operator license# 8061

Lease: Blauer Well # 2-21

Operator: Oil Producers Inc. Of Kansas

County: Rooks 112.32

Address: P.O. Box 8647  
Wichita, Kansas 67208

Well total depth 3456 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 206 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 27 Month: July Year: 1995

Plugging proposal received from: Mike

Company: Oil Producers Inc. Of Kansas Phone:

Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 01 1995  
9/1/95

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 12:00 P.M., Day: 27, Month: July, Year: 1995

Actual plugging report: 8 5/8" set at 206' cwc with 130 sxs. 5 1/2" set at 3422' with 150 sxs. O.H. Arb. 3432' - 3452'. Critical area control shots at 1480' and 830'. Squeezed 5 1/2" with 300 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 200#. Close in P.S.I. 200#. Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I. 500#. Close in P.S.I. 200#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X NO  
Plugged through TUBING, CASING. Elevation: 1983 GL

INVOICED

I did not observe the plugging.

Carl Goodrow  
(agent)

DATE 9-6-95

INV. NO. 43409