

6 030805

PLUGGED NOV 7 1986

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-21,747 0000

SESE NW, SEC. 21, T. 7 S, R. 19 (W)

2970 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8914

Lease Name SCHNEIDER Well # 4

Operator: H&C OIL OPER. INC.

County ROOKS 111.93

Name & Address P.O. Box 86

Well Total Depth 3444' feet

PLAINVILLE, KANSAS

Conductor Pipe: Size _____ feet

67663

Surface Casing: Size 8 5/8 feet 310'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KEISO CASING License Number 6050

Address CHASE, KANSAS

Company to plug at: Hour: AM Day: 7 Month: 11 Year: 19 86

Plugging proposal received from CLAY

(company name) KEISO CASING. (phone) _____

were: 8 5/8" SET @ 310' W/160 SX. 5 1/2" SET @ 3424' W/200 SX. PBTD 3404'

TOP PERE. 3318'. ORDER SAND & COM. CNT. PULL PIPE ORDER 200 SX.

THRIETY MIX. 65/35 PZ 10% GEL 2% DICE 1 5 SX. HULLS B.J. TITAN CNT.

CO. JERRY'S WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 AM Day: 7 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBTD @ 3404 TO 3260 + SPOT

5 SX. COM. CNT. ON SAND 4/BAILER - SHOT & PULLED 2180' OF 5 1/2"

TIE ON TO 8 5/8" MIX & PUMP 4 SX. HULLS 200 SX. CNT. MIX. + 1 SX. HULLS

MAX. PSI 500* CLOSE IN 300* PLUG. COMPLETE.

DEC 8 1986
12/8/86
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE 12-9-86

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 15518