

4-032018

11-3

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-21,722 000
70'N.

SE SE SW /4 SEC. 21, 07 S, 19 W
400 feet from S section line
2970 feet from E section line

Operator license# 5352 Lease Schneider well # 3

Operator: Baird Oil Company, Inc. County Rooks

Address: Box 428 Well total depth 3469 feet
Logan, Kansas 67646 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 211 feet

112.74

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 3 Month: November Year: 94

Plugging proposal received from: Jim Baird

Company: Baird Oil Company, Inc. Phone:

Were: Order 150 sxs. 60/40 pozmix - 10% gel - 400# hulls
Allied Cement Company.

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 10 1994
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:15A.M., Day: 3, Month: November, Year: 94

Actual plugging report: 8 5/8" set @ 211' w/165 sxs. cwc. 4 1/2" set @
3480' w/235 sxs. Prod. perms. 3324' - 3454'. Critical area control
shots @ 875' - 1500' - 2100'. Squeezed 4 1/2" w/25 sxs. cement blend
followed by 8 sxs. gel, followed by 125 sxs. cement blend w/300# hulls
to Max. P.S.I. 400#. Close in P.S.I. 200#. Squeezed 8 5/8" w/50 sxs.
cement blend w/100# hulls to Max. P.S.I. 200#. Close in P.S.I. 100#.
Plug complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did [] observe the plugging. Carl Goodrow

INVOICED

DATE 11-29-94
41742
INV. NO.

ND

(agent)
Form CP-2/3