

6 030804

PLUGGED NOV 7 1986

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163^{NA}21533-00-00

C. NENW, SEC. 21, T. 7 S, R 19 (W)

4620 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8914

Lease Name SCHNEIDER Well # 2

Operator: H & C OIL OPER. INC.

County ROOKS 110.83

Name & Address P.O. Box 86

Well Total Depth 3410 3447 um 6/2/86 feet

PLAINVILLE, KANSAS
67663

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 301'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING License Number 6050

Address CHASE, KANSAS

Company to plug at: Hour: AM Day: 7 Month: 11 Year: 19 86

Plugging proposal received from CLAY

(company name) KELSO CASING (phone) _____

were: 8 5/8 SET @ 301' w/ 200SX. 5 1/2" SET @ 3449' w/ 150SX. PBD 3380'

PERF. TOP 3253' ORDER SAND & COM. CNT. Pull PIPE. ORDER

200SX. THRIFTY MIX. 65/35POZ. 10% GEL 2% DICEL 5SX. HULLS B.J. TITAN

JERRY'S WATER TRUCK.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30AM Day: 7 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBD TO 3200' + SPOT 5 SX. COM. CNT.
ON SAND w/ BAILER. SHOT & RILLED 1814' OF 5 1/2" CSG.

TIE ON TO 8 5/8" MIX. & PUMP 4 SX. HULLS 200SX. CNT. MIX. + 1 SX. HULLS.
MAX. PSI. 400# CLOSE IN 200#. PLUG. COMPLETE.

STATE CORPORATION COMMISSION

DEC 8 1986
12-8-86
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-9-86

INV. NO. 15519

Signed Carl Goodrow
(TECHNICIAN)