

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-21718-00-00  
Spot: NWNE Sec/Twnshp/Rge: 28-23S-14W  
660 feet from N Section Line, 1980 feet from E Section Line  
Lease Name: GETTY Well #: 1  
County: STAFFORD Total Vertical Depth: 3896 feet

Operator License No.: 33226  
Op Name: GIANT HOLDING, LLC  
Address: 223 WEST 4TH  
HUTCHINSON, KS 67501

CIBP Size: feet: 3450 WITH 1 SX CMT  
PROD Size: 4.5 feet: 3869 WITH 300 SX CMT  
SURF Size: 8.625 feet: 239 WITH 225 SX CMT

#126 62

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/23/2005 9:00 AM  
Plug Co. License No.: 33204 Plug Co. Name: BASYE WELL SERVICE, INC.  
Proposal Rcvd. from: DENNIS TERWAY Company: GIANT HOLDING Phone: (620) 662-9005

Proposed Plugging Method: SAND OFF TO ABOVE PERFS - THEN 5 SX CMT, 1st PLUG AT 850' 10 SX GEL AND 50 SX CMT. PULL UP TO 30' BELOW SURFACE (270') RUN 50 SX CMT THEN 20 SX CMT ON THE TOP 50', AS PER RICHARD LACEY, KCC.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/23/2005 12:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3450' WITH 1 SX CMT ON TOP WITH DUMP BAILER. PUMP PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 850' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 270' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3770	3774		
3738	3743		
3662	3664		

RECEIVED  
JUN - 6 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID. RECOVERED 1800' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE

6-7-05

TV, NO.

200561672

Form GPC23